



#### **DISTRIBUTION SYSTEM AND LOSSES**

By

### MARRAPU UDAYA BAHNU NAIDU (500024907)

Guided By

# SRI V.RAJKUMAR, Asst. Professor, GITAM UNIVERSITY, VISAKHAPATNAM.

### A DISSERTATION REPORT SUBMITTED IN PARTIAL FULILLMENT OF THE REQUIREMENTS FOR

EXECUTIVE MASTER OF BUSINESS ADMINISTRATION (POWER MANAGEMENT)

OF

UNIVERSITY OF PETROLEUM & ENERGY STUDIES, INDIA

CENTER FOR CONTINUING EDUCATION

UNIVERSITY OF PETROLEUM & ENERGY STUDIES, DEHRADUN.

#### **ACKNOWLEDGEMENT**

This is to acknowledge with thanks the help, guidance and support that I have received during the Dissertation.

I have no words to express a deep sense of gratitude to the management of the APEPDCL for giving me an opportunity to pursue my Dissertation, and in particular Sri P.Raj Kumar, for his able guidance and support.

I must also thank Sri G.Chiranjeevi Rao, Superintending Engineer, Operation, APEPDCL, Vizianagaram and Sri P.Trinadha Rao, Asst .Divisional Engineer, Operation, APEPDCL, Vizianagaram for their valuable support.

I also place on record my appreciation of the support provided by Sri K. Anand Kumar, Sub Engineer, Town Sub Division, Vizianagaram and other staff in supporting to me to get relevant data.

Signature

Name of the Student: M UDAYA BHANU NAIDU

Residential Address: S/o M. Simhachalam

Narasimhuni Peta Village

Kannam Peta Post Bobbili Mandal Vizianagaram Dist

Andhara Pradesh- 535573

Telephone/ Mobile No: 09492224888 Mail ID: bhanumarrapu@gmail.com



VISAKHAPATNAM \* HYDERABAD \* BENGALURU

Accredited by NAAC with 'A' Grade MHRD 'A' Category University

#### DEPARTMENT OF ELECTRICAL AND ELECTRONICS ENGINEERING **GITAM Institute of Technology**

Gandhi Nagar Campus, Rushikonda, Visakhapatnam – 530 045, A.P., INDIA Phones: +91-891- 2840240, EPABX: 2790101, Fax: 2790399 Website: www.gitam.edu, E-mail: vrajkumar\_eee@gitam.edu

Sri. V. Raj Kumar, M.Tech, MBA (HR), (Ph.D), MISTE

Assistant Professor

Email: vrajkumar\_eee@gitam.edu

coolvrajkumar@gmail.com

Phone: +91 9581267308

#### **Declaration** by the Guide

This is to certify that the Mr Marrapu Udaya Bhanu Naidu, a student of Executive MBA (Power Management) Roll No of 500024907 of UPES has successfully completed this dissertation report on" DISTRIBUTION SYSTEM AND LOSSES " under my supervision.

Further I Certify that the work is based on the Investigation made, data collected and analyzed by him and it has not been submitted in any other university or institution for award of any degree. In my opinion it is fully adequate, in scope and utility, as a dissertation towards partial fulfilment for the award of degree of Executive MBA.

Signature:

Name & Designation: Sri V RAJ KUMAR

Asst. Professor

Address: S/o. Sri V. NARAYANA

FLAT No:501, My Home Apartments

PLOT No:20, GCC Layout

KOMMADI 100Ft ROAD - RIGHT SIDE MADHURAWADA, VISAKHAPATNAM

ANDHRA PRADESH-530048

Mobile No:09581267308

Mail ID: coolvrajkumar@gmail.com

#### **ABSTRACT**

Electric power is the most important commodity in our daily life. Electric power is generated at different voltage levels like 6.6KV, 11KV, 25KV etc. Electric power is transmitted through the transmission Lines. Generally the electric power is generated at 11KV Voltage. The voltage of the generated power is Steped up to 400KV by using the step up transformers and Transmitted through the Lines to the Load centers and at the load centers the voltages are stepped down by using step down Transformers i.e 400/220 KV and 220/132 KV and 132/33KV and 33/11KV. Then the Power is supplied to the Consumers by using the Distribution Transformers and by LT Lines. The Power Transmission i.e from 400KV to 33KV Lines system comes under Transmission System and losses in these lines are only Technical losses (mainly I²R Losses), which are very less.

Where as in Distribution System, the losses consists of Technical and Commercial Losses. The technical losses comprises of line losses (I<sup>2</sup>R Losses), losses in the equipment (Distribution Transformers Losses), Improper size of conductor and bad workmanship and commercial losses mainly because of defective metering, improper billing and pilferage of energy. The Technical losses in Distribution System can be reduced by load balancing of Distribution Transformers and preventive maintenance of Distribution Transformer structures and lines etc. and Commercial losses can be reduced by providing of High accuracy meters to the services and proper inspection of low specific consumption services.

This project is mainly aimed at identifying the reasons for technical and commercial losses in the distribution system and to know the remedies to reduce the technical and commercial losses and also to get idea on Distribution lines. In this project a 33/11 KV sub station is considered on pilot basis which consists of 4 Nos out going 11KV distribution feeders namely 1) 11KV Kothapeta, 2) 11KV Gajularega, 3) 11KV B. Koneru Town 4) 11KV Tank Bund feeders were taken and the input and sales of the above feeders were observed and the technical and commercial losses on these feeders are calculated.

### TABLE OF CONTENTS

| Chapter -1  | Introd | luction of Project                                    | 1  |
|-------------|--------|---|----|
|             | 1.1    | Introduction  | 1  |
|             | 1.2    | Sub Station   | 2  |
|             | 1.3    | Distribution System                                   | 5  |
| Chapter – 2 | Losses | s in Distribution System                              | 8  |
|             | 2.1    | Energy Audit  | 8  |
|             | 2.2    | Net Work Design                                       | 8  |
|             | 2.3    | Factors Contributed to high technical losses.         | 8  |
|             | 2.4    | Reasons for commercial loss                           | 11 |
| Chapter – 3 | Techn  | ical loss reduction in Distribution system            | 13 |
|             | 3.1.1  | Reduce Over Loading of Distribution Transformers      | 13 |
|             | 3.1.2  | Over-rated Distribution Transformers and              |    |
|             |        | their Under-Utilization                               | 13 |
|             | 3.1.3  | Load Balancing of Distribution Transformers.          | 13 |
|             | 3.1.4  | Distribution Transformers Located at Load center      | 13 |
|             | 3.1.5  | Bifrucation of the Distribution lines.                | 14 |
|             | 3.1.6  | Preventive Maintananace of DTRs and LT Lines          | 14 |
|             | 3.1.7  | Amorphous Core Transformers                           | 14 |
|             | 3.1.8  | Removal of Idle DTRs                                  | 14 |
|             | 3.1.9  | Proper Tap Position of OLTC                           | 14 |
|             | 3.1.10 | Proposing of New Sub Stations                         | 14 |
|             | 3.1.11 | Relieving over load on the Feeders                    | 15 |
|             | 3.1.12 | High Voltage Distribution System                      | 15 |
|             | 3.1.13 | Providing of three phase DTRs inplace of 1 phase DTRs | 15 |

|            | 3.1.14 | Running 2 <sup>nd</sup> LT Circuit for LT Lines  | 15 |
|------------|--------|--|----|
|            | 3.1.15 | Improvement of Power Factor  | 15 |
|            | 3.1.16 | Utilization of proper Size of Conductors   | 16 |
|            | 3.1.17 | Avoid the loose connections and Tightening the jumpers                                   | 16 |
|            | 3.2    | Remedies for commercial loss reduction   | 17 |
|            | 3.2.1  | Educate the consumers to avoid the Direct tapping  | 17 |
|            | 3.2.2  | Providing AB Cable in theft / Interruption Prone Areas                                   | 17 |
|            | 3.2.3  | Tackling Power Theft   | 17 |
|            | 3.2.4  | Replacement of Defective meters, and monitoring of spot billing and collection functions | 20 |
| Chapter -4 | Calcu  | lation of line losses  | 25 |
|            | 4.1    | History Sheet of 11KV Kothapeta feeder   | 26 |
|            | 4.1.1  | 11KV Kothapeta Feeder Sketch   | 28 |
|            | 4.1.2  | 11KV Kothapeta feeder Regulation Chart   | 29 |
|            | 4.1.3  | Technical Loss Calculation of 11KV Kothapeta feeder                                      | 30 |
|            | 4.2    | History Sheet of 11KV Tank Bund feeder   | 34 |
|            | 4.2.1  | 11KV Tank Bund Feeder Sketch.  | 36 |
|            | 4.2.2  | 11KV Tank Bund feeder Regulation Chart   | 37 |
|            | 4.2.3  | Technical Loss Calculation of 11KV Tank Bund feeder                                      | 38 |
|            | 4.3    | History Sheet of 11KV Gajularega feeder  | 43 |
|            | 4.3.1  | 11KV Gajularega Feeder Sketch  | 44 |
|            | 4.3.2  | 11KV Gajularega feeder Regulation Chart  | 45 |
|            | 4.3.3  | Technical Loss Calculation of 11KV Gajularega feeder                                     | 46 |
|            | 4.4    | History Sheet of 11KV B.Koneru Town feeder   | 52 |
|            | 4.4.1  | 11KV B.Koneru Town Feeder Sketch   | 54 |
|            | 4.4.2  | 11KV B.Konem Town feeder Regulation Chart  | 55 |

|              | 4.4.3 Technical Loss Calculation of 11KV B.Koneru Town                           |    |  |  |  |  |
|--------------|--|----|--|--|--|--|
|              | Feeder   | 56 |  |  |  |  |
| Chapter – 5  | LOSS CALCULATIONS OF 11KV FEEDERS  | 61 |  |  |  |  |
| Chapter – 6  | Feasibility Study  | 70 |  |  |  |  |
|              | 6.1 Technical loss calculation of 11KV Kothapeta feeder with 34 Sqmm Conductor   | 70 |  |  |  |  |
|              | 6.2 Technical loss calculation of 11KV Kothapeta feeder with 55 Sqmm Conductor   |    |  |  |  |  |
|              | 6.3 Saving of energy due to providing of second LT Circuit.                      | 78 |  |  |  |  |
|              | 6.4 Saving of energy due to conductor replacement and revenue return calculation |    |  |  |  |  |
| Chapter -7   | Conclusion   | 80 |  |  |  |  |
| Bibliography | and References   | 81 |  |  |  |  |

#### 1. INTRODUCTION OF PROJECT

1.1 INTRODUCTION: Distribution System is the network used to supply the electric power to the consumers. Distribution System is very essential in the electrical power system. Today in our daily life power is becoming the most important thing. As the technology is developing all the equipments were came into market and are useful to our daily activities i.e lifts, electric cookers, washing machines, heaters, etc and electrical trains in transportation point of view and most advanced soft ware system i.e Computers etc and all industries which are used to manufacture equipments and also provide employment to the peoples, Agriculture all were primarily depends on electric power. So we can't do any thing with out electric power and we can't imagine our daily life without electric power.

Today we are facing the problem of shortage of electric power. The generated power in India is not met with the demand of electric power. So it has two solutions one thing is to generate more power which is very costly affair and another is to reduce the losses in the present system. Distribution system should be aimed at to provide quality power supply to the consumers with minimum interruption. Our project mainly aimed at reducing the losses in distribution system and to provide quality power.

1.2 Sub Station: In Distribution network, A Sub Station is a component of power system which receives electric energy at a relatively higher voltage and delivers energy to the consumers at low voltage. It is a link between the Transmission and Distribution System and converts higher voltage electric power into low voltage electric power.

Depending upon the physical features which in fact are governed by the Operating voltages, the sub stations are mainly classified as 1)Out Door 2)IN Door 3)Pole Mounted.

Normally for the voltages 33KV and above, out door substations are recommended because of the large air clearance is required. All the equipments lies open in the air. Such Sub Station situated near a power station (Step Up Station) or near a large load centre (Step down Sub Station)

The equipment in the indoor sub station lies in a room. The operating voltages are 400V, 3-phase, 4 wire, LT and HT Voltages may range any thing between 3.3KV to 11KV. These Sub stations are located in Towns.

Pole mounted Sub Stations are step down sub stations where all the equipment is mounted on poles. The Sub Station is used whenever a high voltage line is running and from it a small load such as a village or a small locality or factory is to be supplied.

These Sub stations are quite simple and cheap as no building for housing the equipments is required. The main disadvantage of such sub station is that they are low capacity usually up to 500KVA as the size of the transformer for larger capacity becomes quite big and it cannot be mounted on poles.

**1.2.1 Bus Bar System :-** The bus bar system affects the sub station design to a large extent . Some of the systems are used are given below.

<u>Single Bus Bar System :-</u> This system is simple and cheap as it needs minimum number of circuit breakers. It is normally used for small AC Circuits.

The main disadvantages of this system are 1) A fault on the bus bar will completely shut off the supply to the feeder 2) Maintenance of the bus bar will require complete shut down of the supply to the feeders.

<u>Sectionalized Single Bus Bar System :-</u> Each section can be Operated independent of the other sections. Fuller advantage of the scheme can be obtained if the incoming and the out going feeders are evenly distributed on the sections. Each section can be completely shut down for maintenance or repair with out interfering with other sections.

<u>Duplicate bus bar :-</u> In the more important sub stations the use of duplicate feeders is almost universal. The advantage of the scheme from an operation and maintenance point of view more than out weight the additional cost.

In this system each load can be fed from either bus. Maintenance and repairs on any bus is easier. The in feed and load circuits may be divided into two separate groups, if required from operational point of view.

1.2.2 ) Sub Station Grounding:— In an electrical substation grounding is provided to all the equipments structures and installations so that it can provide a path by which grounding currents are conducted to remote areas. It is there for very important to see that the su station grounding has a low resistance adequate current carrying capacity and safety of personal operating in the sub station is assured. It is very important to see that the grounding resistance is kept at a low value so that rise in ground potential remains with in safe limits for personal safety. The other reasons for sub station grounding is as follows.

- The neutral of the Transformers , reactors or capacitor ( if connected in star ) are provided in ground connection.
- 2) Maintenance of equipment becomes safe if these equipments are discharged through ground, other wise there is a possibility of experiencing electric shock.

- 3) The Over voltage protection devices like lighting arrestors, rod gaps should discharge to the ground when ever these experience over voltages.
- 4) To ensure safety to Operating personnel by limiting potential differences that can exist in a sub station.
- 5) To provide a sufficiently low resistance path to ground to minimize rise in ground potential with respect to remote ground.

The Sub Station grounding system mainly consists of either stranded galvanized steel wires buried into the ground up to the depth of 30 to 45 cm and there are ground rods to which these wire are brazed so that it forms a continuous grid system also known as mat. Some times more than one ground rod is used as these form parallel circuit and effective earth resistance is reduced. It is to be noted that continuous wire surrounds the grid perimeter to enclose as much ground as possible and to prevent current concentration and thus high gradients at the ground wire terminals. With in the grid, wires are buried in parallel lines and with uniform spacing of about 3m X 6m. All these substation equipments and structures are connected to the ground grid with thick conductor to minimize the grounding resistance, and limits the potential between equipment and the ground to a safe value under all operating conditions. All Sub station fences are built inside the ground grid and attached to the grid at short intervals to protect the public and operating personnel. One can always see the surface of the sub station covered with concrete to the potential gradient when large currents are discharged to ground and also to increase contact resistance to the feet of personnel in the sub station. Due to this step potential becomes negligibly small and personal safety is assured. It is found that when an extra high voltage transmission line is passing through a field and the ground of the field is conducting because of soft or moist soil, the animals grazing in the field and moving radially to the transmission tower get electrocuted where as the one moving round the tower the animal is moving along equipotential points where as one moving radially has a high step potential and gets electrocuted.

The ground potential rise depends on various factors eq diameter and length of conductor, spacing between each conductor, fault current, ground system resistance, soil resistivity, System voltage etc.

According to IEEE standard 80-1976 , the grid resistance to ground is given as  $R = \rho/4r + \rho/L$ .

Where R is grid resistance to ground

L is the Length of grid conductors in Ohm - m.

r is the radius in m of circle with area equal that of grid.

#### 1.3. Distribution System :-

Distribution System has two components 1) Feeder 2) Distributor

1.3.1 Feeder: A Feeder in a distribution net work is a circuit carrying current from a main sub station to a secondary sub station, such that the current loading is the same all along its length.

Therefore the main criterion for the design of a feeder is its current carrying capacity.

**1.3.2** ) Distributor :- A Distributor has variable loading along its length due to the service connections, tapped off at intervals by the individual consumers. The voltage variation at consumers terminals must be with in +/-5 % in order to avoid un satisfactory operation of equipment. A reduction in voltage will adversely effect the output of the induction motor of light from a filament lamp. Therefore the main criterion for the design of a distributor is the voltage drop., which must be kept within certain limits.

The distribution system occupies an important place in any electric power system. The effectiveness with which it achieves its objective of distributing electric energy to various consumers, is measured in terms of voltage regulation, flexibility, security of supply efficiency and cost.

#### 1.3.3) Types of Distribution System:-

Depending upon the type of supply, distribution system can be classified as follows.

- 1. A.C Single phase (Single phase loads only)
- 2. 3-phase, 3 Wire (3 Phase loads only)
- 3. 3 Phase, 4 Wire (all types of loads)

The distribution system can be classified depending upon the connections . These are the following two systems.

- 1) Radial System.
- 2) Ring Mains System.

Radial System:— The energy distribution is originally through radial system. The advantages of radial system are its simplicity and low cost, which result from a straight forward circuit arrangements where a single or radial path is provided between the consumer and the source or bulk power supply. With such an arrangement, the amount of switching equipment required is small and the protective relaying is simple. The major disadvantage of radial system is its lack of security of supply. When a fault occurs on any section of the feeders, remaining consumers on the healthy section feeders will be with out supply for a considerable period. The radial system is normally used for rural distribution these days.

Ring Mains System: The system is most used frequently, to supply bulk loads such as small industrial loads and the medium or large commercial buildings where continuity of supply is of considerable importance. When an inter connector is used in a ring main system it reduces the voltage drop between the points to which it is connected. The ring mains system is used for urban distribution in contrast to the radial system.

A.C Distribution Single phase: In Case of a AC Distribution as the distance separation between the wires is relatively smaller as compared to the over head lines, the resistance

component is normally higher than the inductive reactance component and hence both R and X Components contribute to the voltage drops. Also the current is at some phase angle with respect to the voltage, and there fore the both the components i.e in phase and quadrature component of the current contribute to voltage. If the current is

I (cos  $\Phi$  - j sin  $\Phi$  ) and the series impedence is (R+jX).

Drop = 
$$IZ = (I \cos \Phi - JI \sin \Phi) (R + JX)$$
  
=  $IR \cos \Phi + IX \sin \Phi + j IX \cos \Phi - j IR \sin \Phi$ 

for the most of the systems IX  $\cos \Phi \approx IR \sin \Phi$ 

There for drop  $IZ = IR \cos \Phi + IX \sin \Phi$ .

3-Phase, 4Wire System: Usually A.C. Distribution is through 3-phase 4 wire system as there is possibility of single phase and 3-phase loads in almost in every locality. The fourth wire is the return conductor for all the three phases, which connected to the star point of the load and the neutral of the supply system. Under the balanced condition the net current through the neutral is zero. The electric utilities try to balance the load on each phase, as the balanced load voltage results due to unbalanced load voltage results due to unbalanced loading which is dangerous for the proper working of 3-phase induction motors. Yet it is practically impossible to obtain the perfect balancing, some amount of unbalance is always present in the system. The unbalance is due to the presence of single phase loads.

#### 2. LOSSES IN DISTRIBUTION SYTEM

#### 2.1 Energy Audit :-

The first step is to carry out the energy audit of the distribution system to segregate and pinpoint the commercial and technical losses. Having identified the causes of technical losses, we must analyze all the causes of the technical losses and develop them in the form of several DPRs (detailed project reports). Finally a list of projects showing gestation period, investment, and benefits must be listed so that the projects can be prioritized. The prioritization must be such that the external funding requirements are kept at minimum.

#### 2.2) Network Design :-

The projects must take into account the future developments and changes in the ground realities (such as changes in demand due to increase in population and improvements in standard of living). One must be aware that as the population is increasing there would be more people living per square kilometers. The same people are going in for new appliances, which use electricity. Thus the transformer loading is going to go up. The current being carried by the conductors would also increase. These two would have impact on transformer losses and I<sup>2</sup>R losses. Thus any time after 5 years or 10 years, there may be a need to revamp the network. How to envisage, what factors must be considered today, and how to design today's network so that changes required in network should be minimal leading to less investment. Otherwise, the technical losses would go up.

#### 2.3 ) Factors Contributing High Technical Losses :-

The main factors that contribute for high technical losses are usage of lower size conductors,

low voltage pockets,

lack of reactive power control, etc.

The methods to reduce technical losses in the order of priority based on cost impact are Re configuration (change over of loads or feeding source). Re conductoring (Replacing existing conductor by higher size or conversion of single to double circuit).

Shunt or series capacitor installation (switched and fixed).

Auto voltage booster.

Additional link lines.

Combination of two or more of the above.

As a last resort to go in for another sub-station followed up by reconfiguration.

#### The Following are the main factors for the Technical loss in Distribution System:

#### 2.3.1) Over Loading of Distribution Transformers:

All the Distribution Transformer should be loaded upto 80% of its rating only . if DTR is loaded more than 80% of its capacity, the full load losses will increases and temperature gets raise and the DTR may fail at any time. The consumers may also suffer from low voltage problem .

#### 2.3.2 Improper utilization of Distribution Transformers :-

Studies on 11 KV feeder have revealed that often the rating of distribution transformer is much higher than the maximum KVA demand on the feeder. Over rated transformers draw an unnecessary high iron losses. In addition to this iron losses in over rated transformers the capital costs locked up is high.

#### 2.3.3 Un balanced loads on Distribution Transformers :-

Load should be equally shared between the all the three phases in a Distribution Transformer. If it is not done the consumers who are getting supply from the over loaded phase suffers from low voltage problem. Line losses also increases in that phase.

# 2.3.4 Distribution Transformers not Located at Load center on the Secondary Distribution System:-

Often Distribution Transformers are not located centrally with respect to consumers.

Consequently, the farthest consumers obtain an extremity low voltage even though a reasonably

good voltage levels maintained at the transformers secondaries. This again leads to a higher line losses.

#### 2.3.5) Lengthy Distribution lines:-

In practice, 11 KV and 415 volts lines, in rural areas are hurriedly extended over long distances to feed loads scattered over large areas. Thus the primary and secondary distribution lines in rural areas; by and large radially laid, usually extend over long distances. This results in high line resistance and therefore high I2R losses in the line.

2.3.6) Non Maintananace of DTRs and LT Lines: All the Distribution Transformers and LT Lines should be properly maintained periodically. There should not be any looses connections and jumperings etc in lines which causes unnecessary line losses. There should not be any defective AB Switches and loose terminations at sub stations and DTRS as the loose terminations causes the power loss.

**2.3.7)Improper Tap Position of OLTC:** Tap position Should be properly maintained other wise voltage fluctuation may occurs. During off load periods tap position should be lowered and during on load periods the tap position should be higher other wise low voltage problem may occurs which in directly causes full load losses.

**2.3.8) over loading on the Feeders :-** If any feeder is overloaded the consumers may be suffer from the frequent interruptions of the supply due to the trippings of the feeders and the low voltages problems may occurs to the consumers who are at tail end and also copper losses increases due to the low voltage.

2.3.9) Low Voltage (less than declared voltage) Appearing at Transformers and Consumers Terminals: -Whenever the voltage applied to induction motor varied from rated voltage, its performance is affected. Within permissible voltage of +/- 6% of the affect practice, the supply voltage varies by more than 10% in many distribution systems. A reduced voltage in case of induction motor results in higher currents drawn for the same output.

For a voltage drop of 10%, the full load current drawn by the induction motors increase by about 10% to 15% the starting torque decreases by nearly 19% and the line losses in the distributor increases by about 20%. As the bulk load of rural areas and small scale industrial areas consists of induction motors, the line losses in the concerned distribution systems may even touch 20%.

- 2.3.10) Lenghty LT Lines :- Lengthy LT Lines makes the low voltage problem to the consumers and also make the high losses.
- **2.3.11)** Low Power Factor:-In most LT distribution circuits, it is found that the PF ranges from 0.65 to 0.75. A low PF contributes towards high distribution losses. For a given load, if the PF is low, the current drawn is high. Consequently, the losses proportional to square of the current, will be more.
- **2.3.12)** <u>Inadequate Size of Conductors:-</u> Rural loads are usually scattered and generally fed by radial feeders. The conductor size of these feeders should be adequate. Because of lower size conductor line losses also increases.
- 2.3.13) Bad Workmanship Resulting in Poor Contacts at Joints and Connections:- Bad Workmanship contributes significantly towards increasing distribution losses. The joints in the conductors makes the high copper losses.
- 2.4 ) Reasons for commercial loss: The commercial losses in power distribution utilities involves the following reasons:
  - 1. Direct tapping by the non customers.
  - 2. Pilferage by the existing customers.
  - 3. Defective metering, billing and collection functions.

#### 2.4.1) Direct tapping by non customers:-

In certain areas, direct tapping of power by non customers is widely prevalent. This is mainly in domestic and agricultural categories. Geographical remoteness, mass basis for theft, poor law enforcement capability and inaction on the part of utility are helping this phenomenon.

These factors result in poor voltages, burnt motors, failed transformers and dried crops.

#### 2.4.2) Pilferage of power by the existing customers:-

Theft by the existing consumers is the predominant cause of loss of revenue to the electrical utilities. Almost all categories of the consumers are involved in this.

#### 2.4.3) Totally bypassing the meter:-

The meter is not tampered. It is like direct tapping. From the supply lines, the tapping is made and part or full load is fed from that. This can be proved only when it is observed at the time of inspection. The consumer can erase all traces of theft if the inspection is known in advance.

#### 2.4.4) Tampering the meter:-

- 1. Bypassing at the terminal block.
- 2. Damaging the meter internal mechanism.

There are umpteen methods for tampering the meter. New methods are being constantly evolved. All these makes the commercial losses.

- <u>2.4.5) Defective meters :-</u> Genererally after some period of time the meters may struck up or due to the overload usage by the consumers the meters may burnt. This causes the problem in the recording the units by the consumer. This also the reason for the commercial loss.
- **2.4.6)** Improper Billing:— In some rural areas billing is not properly done. This makes the incorrect energy audit calculation. this is also comer under the commercial loss.

## 3) The Following are the steps to be taken for the Technical loss reduction in Distribution System:-

#### 3.1.1) Reduce Over Loading of Distribution Transformers:-

All the Distribution Transformer should be loaded upto 80% of its rating only. No Distribution Transformers should be loaded more than 80% and if found any DTR loaded more than 80% of its rating, propose another Distribution Transformer or shift the existing loads to near by DTR with lesser loading.

#### 3.1.2) Over-rated Distribution Transformers and hence their Under-Utilization:

The rating of distribution transformer should be judiciously selected to keep the losses with the permissible limits. For an existing distribution system the appropriate capacity of distribution transformer may be taken as very nearly equal to the maximum KVA demand at good PF (say 0.85) Such an exercise has been carried out for a number of distribution systems and transformers with capacity of 25, 63, 100, 160, 315 KVA and standardized for different with power factors and diversity factors.

#### 3.1.3) Load Balancing of Distribution Transformers:-

Load should be equally shared between the all the three phases in a Distribution Transformer. If it is not done the consumers who are getting supply from the over loaded phase suffers from low voltage problem. Line losses also increases in that phase.

# 3.1.4) Distribution Transformers should be Located at Load center on the Secondary Distribution System:-

In order to reduce the voltage drop in the line to the farthest consumers, the distribution transformer should be located at the load center to keep voltage drop within permissible limits.

#### 3.1.5) Bifrucation of the Distribution lines:-

Due to the lengthy lines results in high line resistance and therefore high I2R losses in the line. It is better to reduce the length of the lines by bifurcations of the feeders and also by providing interlinking lines etc to reduce the losses in the system.

3.1.6) Preventive Maintananace of DTRs and LT Lines: All the Distribution Transformers and LT Lines should be properly maintained periodically.

3.1.7) Amorphous Core Transformers :- Recently DTRs with amorphous core have entered Indian market which has low constant losses The core (magnetizing or no load losses) get substantially reduced. However the high cost is coming in the way for large scale introduction. Efforts are being made to make amorphous core material indigenously and the cost is expected to go down considerably

3.1.8) Removal of Idle DTRs:- No Distribution Transformer should be Kept idle. due to this some power was wasted in the form of Constant losses i.e Iron losses and small amount of copper losses also.

3.1.9) Proper Tap Position of OLTC:— As per the requirement of the voltage and also as per the load the tap position may be changed. The proper voltage level is maintained by operating an "onload-tap changing" in the power transformers situated at high voltage sub-stations and providing on the 11 KV feeders a combination of switched capacitors and automatic voltage regulators.

Further, the "off load tap changing" in distribution transformers is adjusted prior to the commencement of agricultural load season, which is readjusted before the one-set of monsoons when the rural load is small the off-load tap changing gear is available

3.1.10) Proposing of New Sub Stations: If the Length of the 11KV lines are very large better to provide new 33/11KV Sub-Stations for providing of better voltage to the consumers. If the length of the 11KV Lines are very large it forces the system to the low voltage which directly causes the increased losses. To avoid this it is better to provide 33/11KV Sub stations at load centers.

- 3.1.11) Relieving over load on the Feeders:- No feeder should be overloaded and found if any, bifurcate them by providing interlinking lines. If there is no provision for the interlinking lines in the field, it is better to run the parallel line to the existing line and distribute the existing load on the both the feeders which reduces the line losses.
- 3.1.12) High Voltage Distribution System :- The distribution systems shall be at high voltage and the L.T. system shall be the least or eliminated as far as possible. High voltage distribution systems by converting existing Low voltage distribution system reduces the technical losses appreciably. This can be explained by one single illustration that for a 100 KVA load the amperage at 11KV is 5 Amps where as it is 140 Amperes at L.T. voltage of 415 Volts.
- 3.1.13) Providing of three phase DTRs inplace of Single phase DTRs:—All the single phase DTRS should be replaced with three Phase DTRS there by reducing the iron and copper losses.

  And Load carrying capacity also more for a three phase DTR than by a single phase DTR.
- 3.1.14) Running 2<sup>nd</sup> LT Circuit for LT Line Carrying grater than 75Amps and Length greater

  than 0.5KM: Lengthy LT Lines makes the low voltage problem to the consumers and also make the high losses. Hence it is better to Provide 2<sup>nd</sup> LT Circuits for the LT Lines where length of the LT Line is greater than 0.5Km and current carrying is greater than 75A

#### 3.1.15) Measures for improvement of Power Factor:-

The power factor can be improved by the following methods

This can be done by application of shunt capacitors.

Shunt capacitors can be connected in the following ways:

Shunt capacitors are connected on the secondary side (11 KV side) of the 33/11 KV power transformers.

ii). Line losses in LT distribution lines may also be considerably reduced by installing shunt capacitors of optimum rating at vantage points.

The optimum rating of capacitor banks for a distribution system is  $2/3^{rd}$  of the average KVAR requirement of that distribution system. The vantage point is at  $2/3^{rd}$  the length of the main distributor from the transformer.

iii) A more appropriate manner of improving this PF of the distribution system and thereby reduce the line losses is to connect capacitors across the terminals of the consumers having inductive loads. The extent of reduction of line losses in this manner depends mainly on the extent to which the PF of consumers is improved. In this case, the capacitor is connected in parallel to the terminals, the capacitors being switched on and off together with the equipment itself.

Many electricity supply authorities are modifying their tariff conditions to make it compulsory for the consumers to provide capacitors for all types of installations with connected loads of 5 HP and above.

By connecting the capacitors across individual loads, the line loss is reduced depending upon the extent of PF improvement.

#### 3.1.16) Utilization of proper Size of Conductors:-

The size of the conductors should be selected on the basis of KVA X KM capacity of standard conductor for a required voltage regulation. Presently all the 11KV Urban feeders were provided with 55 SQmm Conductor. But it in some rural areas 11KV lines was with 34 Sqmm Conductor only and better to replace the lower size conductor with higher size as per the voltage level.

#### 3.1.17 ) Avoid the loose connections and Tightening the jumpers:-

- i) Proper jointing techniques should be used to ensure firm connections.
- ii) Connections to the transformer bushing-stem, drop out fuse, isolator, and LT switch etc. should be periodically inspected and proper pressure maintained to avoid sparking and heating of contacts.

iii). Replacement of deteriorated wires and services should also be made timely to avoid any cause of leaking and loss of power.

#### 3.2) Remedies for commercial loss reduction:-

The reduction in commercial losses in power distribution utilities involves the following steps:

- 1 Educate the consumers to avoid the Direct tapping.
- 2. Providing of AB Cable in the theft prone areas.
- 3. Tackling of power theft.
- 3. Replacement of Defective meters, and monitoring of spot billing and collection functions.

#### 3.2.1 Educate the consumers to avoid the Direct tapping .:-

Some amount of public relations work by the utility is needed to tackle this menace. It is to be widely publicized that theft will increase the tariff for the genuine consumers, result in poor voltages, burnt motors, failed transformers and dried crops. The scarce resources of the state, meant for social welfare, are diverted to feed these power thieves.

Some change in the value systems of the society is also needed. The opinion makers and social leaders are to be involved to effectively tackle this massive social evil.

Direct theft is an insult and thus a challenge to the utility engineer. It speaks volumes about the inefficient functioning of the company. Tackling it brooks no delay. Other works can be stopped and total attention diverted for this purpose.

3.2.2) Providing AB Cable in theft / Interruption Prone Areas: Generally in rural areas consumers were committed to the theft i.e they may utilize the supply with out meters or by directly tapping from the existing LT lines, In those areas it is better to replace the conductor with the AB Cable where the chances were very less for theft of energy

The details of legislation, procedure to inspect, detect and prosecute the criminals are discussed separately.

3.2.3 )Tackling Power Theft: Theft of energy is almost the single cause of all ailments afflicting power utilities. The transformer failures, breakdowns, poor collection of revenue, financial

losses, the wide spread customer dissatisfaction, the recurring crisis in summer crop period, the poor creditworthiness resulting in inability to raise the funds needed for the required growth, increased technical losses and the corroded integrity of employees... are all the manifestations of the theft. These can include low frequency, cascade trippings in grid and unscheduled shutdowns. The whole bad image of the utilities is due to theft. In the districts where theft is non existent, the utility is having good reputation and vice versa.

#### Magnitude

In the nation around Rs.40, 000 crores are lost by the utilities annually. In any other sector - be it private, public or joint - or be it in the state or the nation — no other company is losing money in this magnitude. In the world over power utilities are making profits. Those shares are considered as retired people's and widows' shares. They make money whether it is famine or flood, though not excess profits. With just half of this amount employment guarantee scheme is being planned. Within two and half years of this money all the 444 pending irrigation projects can be completed, irrigating millions of acres.

#### Beneficiaries

The beneficiaries of theft are anti social elements, immoral political abettors and unscrupulous industrialists. The bad money is driving out the good money from the market. This is a social menace crippling all other developmental and social welfare activities.

#### Forerunner

A.P., as usual, is the forerunner in recognizing this menace and established a separate wing for pilferage detection as early as in early sixties. Even now in some states there is no such separate cadre for detecting pilferage. The local officer, either operation or construction or MRT, is very much preoccupied with his busy day-to-day activities and cannot spare time for detection of theft. The social and political influences are more easily brought on the local officer who has, perforce, to deal with them in other for regularly. A specialized knowledge on the functioning of various meters and the latest M.O. of power theft can be acquired by a dedicated band only.

Personnel: While filling up DPE (Detection of Pilferage of Electricity) wing extra care is to be taken so as to have only officers having the required technical knowledge, tact, tenacity and integrity: at times, they would be detecting, dealing and deciding the cases involving crores of rupees on the spot.

**Opportune time:** With the advent of Electricity .Regulation Commission, the functioning of electrical utility is now transparent. Its financial performance is in public gaze. The necessity of eradicating theft is realized by all.

After realizing this, state governments are coming out in a big way to support the electrical engineers entrusted with the arresting of power pilferage. The opposition parties, farmers' organizations, colony welfare associations and industrialists are one with us in this errand. If we do not move now, our very sincerity will be debated. One cannot be guilty of inaction on the notion that attempting to control theft is dangerous to ones self. Actually the test of ones loyalty to the organization is the number of cases she books in a month.

**Functions:** Though originally **DPE** wing was meant only for detection of pilferage, of late its functioning is covering many other facets:

- 1. Malpractice.
- 2. Back billing.
- 3. Excess connected loads.
- 4. Poor power factors in all categories.
- 5. Running of captive generator sets without adequate safety arrangements etc.
- 6. Non sealing of AB switches, meter boxes, and terminal covers.
- 7. Line losses in selected towns, industrial feeders etc.
- 8. Functioning of border meters, capacitor banks etc.
- 9. Bus, P.T. and C.T. facilities for efficient metering.
- 10. Inspection of high value UDC services.

- 11. Study of MRBs.
- 12. Applying CAT for HT & LT services and inspecting class F services, etc.
- 13. Maintenance of assets by local officers.
- 14. Billing irregularities in transformer repairs, maintenance and construction works.
- 15. Non standard releasing of services.
- 16. Releasing of services in UDC premises.
- 17. Releasing of services in wrong categories.
- 18. Coordinating massive inspections with all engineers and APTS personnel wherever required.
- 19. Involvement of employees in various irregularities.
- 20. Payment and billing pattern of services of VIPs.

# 3.2.4 ) Replacement of Defective meters, and monitoring of spot billing and collection functions.

These losses are not due to any deliberate actions of the customers.

They are due to internal shortcomings and hence are that much easier to tackle.

They thrive due to the fact that the boards did not function on commercial lines though they were supposed to do so.

#### Metering:-

There are many services unmetered. A large scale drive is necessary to bring all unauthorized consumers on to the rolls. Such drive in Andhra Pradesh during a single month of June 2000 resulted in metering of 20 lakh new consumers and regularization of 2.57 lakh agricultural services.

Instructions are to be issued to not to release any new service without meter. All the existing unmetered services shall be stopped to be so immediately. The utility should concentrate on purchasing of adequate quantity of meters both for fresh services and for replacement of the

defective meters in the existing services. Purchasing of other materials shall be given low priority, if the financial position demands it. Other materials can be purchased by the consumers.

Unmistakable instructions are to be given on the standards to be adopted at the time of releasing of new services. The service wire is to be brought in a pipe which shall be visible throughout and end in the meter box with a gland. The meter, preferably electronic, shall be fixed in a box visible and accessible from outside. The meter shall be fixed in a box at a height of 5'to 6' from the ground. The particulars of seal bits used are to be noted and attested by the consumer. Proper earthing is needed at the installation. This earth, body earth and neutral are to be clubbed up on the meter board. If all these precautions are taken, possibility for theft and defective metering are reduced drastically.

An exhaustive note on releasing of high value services is given separately.

The meters tend to get sluggish over a period of time. Old meters are to be replaced in a phased manner by high accuracy meters, specially for high value services and at places where the load varies substantially.

C.T. meters are to be adopted in stead of whole current meters for L.T. high value services.

A comprehensive energy audit will pinpoint the areas of high commercial losses. Important services, feeders and towns are to be taken up early for this exercise. Actually, the biggest ever theft case was detected while on one such exercise.

Following are the general defects observed in metering.

- Many stuck up meters are allowed for years.
- For a good number of services, no readings are furnished by the meter reader, at times, continuously.
- Constant nil consumption cases are reported without any comment.
- There are progressive readings in disconnected services.
- There is considerable voltage drop in metering cables.
- The meter capacity and the load have no relation.

- Wrong multiplication factors are adopted. After the M. F. is changed, it is not intimated to the billing agency.
- Fixing of meters at LV Side Distribution Transformers: All the Distribution transformers should be provided with LV Side energy meters. By comparing the input energy with the sum of the distribution transformers energy meters sales we can calculate the losses. By comparing the consumption of distribution transformer LV side meter with the sum of sales of the services existing under this distribution transformer, we can calculate the losses distribution transformer wise and also provision for us to concentrate on high loss distribution transformer.

#### **BILLING:-**

Correct billing and timely serving will go a long away in improving the collections. The normal complaints in the billing process are: non receipt/ late receipt of bills, receiving of wrong bills, wrong reading/ status, table readings and wrong calculations. All these can be avoided in a single go by going for computerized spot billing as is already done in some states. This can be introduced in stages starting from cities. A thorough understanding by the readers on the various statuses of the meter is a sine qua non for the success of the system.

Common billing software adoption is to be achieved so as to have a meaningful control, review, storage and retrieval of the consumer database. Even the application of CAT would be more effective this way.

Monthly billing is to be achieved for the convenience of the consumer and also for psychological reasons. Stringent checks are to be adopted in the billing process so as to plug the leaks.

The first bill is not issued or is issued late in many cases. The customer service number is to be noted on the meter at the time of issue in the section office.

The utilities adopt the last 3 months average in case of abnormal meter status. A meter becomes initially sluggish and then slowly drifts to stuck up position. So the last three months

average would not give a correct picture of the consumption. A study in A. P. revealed that the utilities are annually losing scores of crores on this count alone.

Very high consumption when compared to the similar connected loads indicates unauthorized additional loads. The services, where the standard deviation in consumption is less than 2%, are to be targeted. Similar action when there is abnormal variation. Constantly getting less than minimum in good areas should attract our intention.

<u>Identification and Clubbing of multiple services:</u> Some people may use more than one service for the same premises, because of that consumption was recorded by the two energy meters there by comes under the low slab rate in billing system and also the cost of the energy charges were reduced which is lost to the Distribution systems. Hence it is better to identify those services and merge then into single service.

The power distribution companies have a unique advantage of contacting millions of citizens at least once in a month. This is to be utilized fully to explain the latest initiatives and seek their support in their own interest and in the interest of the company. The Tirupathi based company spared some space in the reverse of the bill to an advertiser and thus the bill making cost is saved.

#### Collection:-

Unbundling and corporatisaion will give a real boost for the collection effort. Every citizen would feel it to be her normal duty to pay for the commodity she purchased. The poor now have a tendency to feel that they have a natural right to enjoy the government bonanza. But even the poorest man will not dream of having a soap freely from the seller. After reforms, there was phenomenal increase both in demand and in collection percentage in A. P.

Increased customer convenience shall be the guiding factor for smooth collections. Drop box facilities and roping in more collection agencies make the lengthy queues vanish. E seva centers are a relief to the customer as around 25 types of bills are accepted in a cool atmosphere at convenient hours in the holidays too. On line facilities like icici bill junction are extended.

Special collection drives, coupled with intensive inspections, in the areas where the payment history was bad, brought terrific results. Effective disconnection of defaulters shall be a norm rather than a chance occurrence. CAT is to be applied and high arrears services are to be targeted. Class F services, where the consumer is availing supply without any payment from last one year are to be initially tackled for more impact. Reversal entries in the case of non paying consumers demand immediate attention.

The worst villages are to be adopted by DPE and vigilance wings and make them as model villages. This will be a spark for others to act.

Every house shall have the service connection no. painted at the pole, gate and meter. In fuse off call offices, before attending a fuse off call, they verify the defaulters' list. Only when these two conditions are fulfilled, the complaint would be attended.

The electricity revenue officials are to work and they are to be pin pointed for poor collections. The revenue recovery act is to be made use of. There shall be compulsory and immediate prosecution in the case of bounced cheques. It is interesting to note that no witness, except the bounced cheque, is necessary for imprisoning the offender promptly, in these cases.

The problem of fraud ever lingers on in the collection process. In one case, a single employee in electricity revenue office could knock off more than one crore rupees in about a year. Computerized monitoring system will help here.

Increased booking of cases on thieves and defaulters will bring real change in collection scenario. Anti power theft police stations (APTS) to deal exclusively with these cases are desirable to have any meaningful effect.

#### 4. CALCULATION OF THE LINE LOSSES

Now Days power sector plays very important role in the development of any nation. Industrial devolpment and Agricultural power sector were mainly depends mainly on the electricity. Power is generated by Conventional energy sources and Non Conventional energy sources. Conventional energy sources includes Thermal power generation and hydal power generation and Nuclear power generation. Non Conventional power generation includes Tidal power generation and solar Power generation and Geothermal power generation, Magneto hydro power generation and etc. 80% of the generated energy in india is due to conventional energy sources.

Remaining 20% is due to the Non Conventional energy sources. But the conventional energy sources are day by day decreasing and in future it may be the severe problem to the country for power generation. So the alternate is to reducing the power consumption so as to extend the time of availability of conventional energy sources.

Power consumption reduction is not easily possible but the losses in the power system can be reduced. Saving of one unit of energy is equivalent to the production of 1.5 units of energy is the slogan in the present power sectors. So Losses reduction in the power sector is very essential in the practical applications. Losses reduction plans are applicable in the Transmission system and also in Distribution system.

In this project to calculate the line losses KPMG methodology is followed. On the part of project line losses of four numbers 11KV feeders namely 11KV Kothapeta, 11KV Gajularega, 11KV B.Koneru Town, 11KV Tank Bund feeders losses in Vizianagaram Town were calculated and also find the technical and commercial losses separately. Here we can Observe the Losses of the above four numbers feeders from April 2014 to May 2015 and also discussed the reasons behind the losses.

#### 4.1) HISTORY SHEET OF 11KV KOTHAPETA FEEDER

| Ţ         |  |                   |   |                     |                       |
|-----------|--|-------------------|---|---------------------|-----------------------|
| ۸.        | NAME OF THE 33/11KV SUB-STATION.               | $\Longrightarrow$ | B.koneru  |                     |                       |
| В         | NAME OF THE EHT SUB-STATION.                   | $\Longrightarrow$ | EHT SS:132/33 KV Von  | itithadi            | S.S.Code: 021111      |
| <b>.</b>  | NAME OF THE FEEDER.                            | $\Longrightarrow$ | 11 KV Kothapeta   |                     | Feeder Code :02111101 |
| <b>).</b> | TYPE OF THE FEEDER                             | $\Longrightarrow$ | Town  |                     |                       |
| E.        | PEAK LOAD IN AMPS.                             | $\Longrightarrow$ | 45 A  |                     |                       |
| F.        | AVERAGE POWER FACTOR.                          | $\Longrightarrow$ | 0.965   |                     |                       |
| <b>3.</b> | SIZE OF THE CONDUCTOR.                         | $\Longrightarrow$ | 55Sqmm AAAC   |                     |                       |
| Η.        | DETAILS OF ALTERNATIVE SUPPLY.                 | $\Longrightarrow$ | 1. RECEIVING FROM<br>2. SENDING TO                              | 11 KV Das           | annapeta P & T        |
| I.        | LENGTH OF 11KV LINE.                           | $\Longrightarrow$ | <ol> <li>Trunk line in KM.</li> <li>Spur Line in KM.</li> </ol> | 1.085 Km<br>0.85 Km |                       |
| J.        | LENGTH OF LT LINE.                             | $\Longrightarrow$ | <ol> <li>Trunk line in KM.</li> <li>Spur Line in KM.</li> </ol> | 11.2 KM<br>6.1Km    |                       |
| K.        | % TECHNICAL LOSSES.                            | $\Longrightarrow$ | 1.93%   |                     |                       |
|           | % REGULATIONS.                                 | $\Longrightarrow$ | 0.69%   |                     |                       |
|           | Names of the villages being fed from this feed | ler ( For Town/M  | IHQ feeder only)f:  |                     | Town                  |
|           | Names of all the Sections being fed from this  | feeder:           |   |                     | D1                    |
|           | No of Distributions being fed from this feeder | r:                |   |                     | 13                    |
|           | Wheteher all sections and distributions have C | Codes in PAA Da   | ta and all consumers are in                                     | ndexed:             | V                     |

#### No. of the DTRs - Capacity wise:

| Capacity    | 250 | 200 | 160 | 100 | 75 | 63 | 25 | Total<br>No. | Total<br>Capacity |
|-------------|-----|-----|-----|-----|----|----|----|--------------|-------------------|
| No. of DTRs | 0   | 0   | 1   | 11  | 0  | 0  | 1  | 13           | 1285              |

Yes

#### Category wise consumers &Sales (Present)

|        | Cat.        | I      | П     | Щ    | IV | V | VI   | VII  | HT | Total  |
|--------|-------------|--------|-------|------|----|---|------|------|----|--------|
| Mai.15 | No. of Scs. | 2624   | 220   | 16   | 0  | 0 | 8    | 11   | 0  | 2879   |
|        | Sales       | 267008 | 62684 | 8711 | 0  | 0 | 2828 | 1405 | 0  | 342636 |
|        | Sp.Con      | 102    | 285   | 544  | 0  | 0 | 354  | 128  | 0  | 119    |


#### II LOSSES THIS YEAR:

| SI.No. | Month  | Input to<br>11KV<br>Feeder | 11KV Direct<br>Sales | Metered Sales | Connected load in AGL services | AGL.Sales | Assessed<br>Units | Total Sales | Loss  | % Loss for the month |
|--------|--------|----------------------------|----------------------|---------------|--------------------------------|-----------|-------------------|-------------|-------|----------------------|
| 1      | 2      | 3                          | 4                    | 5             | 6                              | 7         | 8                 | 8           | 9     | 10                   |
| 1      | Jän.15 | 215640                     | 0                    | 203044        | 0                              | 0         | 0                 | 203044      | 12596 | 5.84                 |
| 2      | Feb.15 | 263760                     | 0                    | 245637        | 0                              | 0         | 0                 | 245637      | 18123 | 6.87                 |
| 3      | Mär.15 | 295000                     | 0                    | 277861        | 0                              | 0         | 0                 | 277861      | 17139 | 5.81                 |
| 4      | Apr.15 | 354560                     | 0                    | 334428        | 0                              | 0         | 0                 | 334428      | 20132 | 5.68                 |
| 5      | Mai.15 | 363120                     | 0                    | 342636        | 0                              | 0         | 0                 | 342636      | 20484 | 5.64                 |

AL SERVICES UNDER FEEDER :-

|                        | services                    |                                 |                                    |                        |                                 |
|------------------------|-----------------------------|---------------------------------|------------------------------------|------------------------|---------------------------------|
| No of metered services | Total HP of metred services | No of un<br>metered<br>services | total HP of Un<br>metered services | Assesed Agrl.<br>Sales | availing 24<br>Hours<br>supply. |
|                        |                             |                                 |                                    |                        |                                 |
|                        |                             |                                 |                                    |                        |                                 |
|                        |                             |                                 |                                    |                        |                                 |
|                        |                             |                                 |                                    |                        |                                 |
| ļ                      |                             |                                 |                                    |                        |                                 |
|                        |                             |                                 |                                    |                        |                                 |

### 4.1.1) 11KV Kothapeta feeder Sketch



### 4.1.2 ) 11KV Kothapeta Feeder Regulation Chart

|             | 0.01 | 0.075 | 0.25 | 0.09 | 0.2 | 0.1 | 0.1 | 0.36 | 0.01 |
|-------------|------|-------|------|------|-----|-----|-----|------|------|
|             | 100  | 100   | 100  | 125  | 200 | 100 | 300 | 160  | 100  |
| 33 / 11kv   |      |       |      |      |     |     |     |      | ·    |
| B.Koneru SS |      |       |      |      |     |     |     |      |      |
| 1x8MVA      | 1285 | 1185  | 1085 | 985  | 860 | 660 | 560 | 260  | 100  |

|       | MOME | ENTS  |        |                                     |               |      |
|-------|------|-------|--------|-------------------------------------|---------------|------|
| SI.No | KVA  | KM    | Total  |                                     |               |      |
| 1     | 1285 | 0.01  | 12.85  |                                     |               |      |
| 2     | 1185 | 0.08  | 88.88  | HT<br>Regulatio <u>0.08566</u><br>n | <u>808.63</u> | 0.69 |
| 3     | 1085 | 0.25  | 271.25 | 100.                                | 00            |      |
| 4     | 985  | 0.09  | 88.65  |                                     |               |      |
| 5     | 860  | 0.20  | 172.00 | Hence, Satisfactory                 | 0.69%         |      |
| 6     | 660  | 0.10  | 66.00  |                                     |               |      |
| 7     | 560  | 0.10  | 56.00  |                                     |               |      |
| 8     | 260  | 0.20  | 52.00  |                                     |               |      |
| 9     | 100  | 0.01  | 1.00   |                                     |               |      |
|       |      | TOTAL | 808.63 |                                     |               |      |

# 4.1.3) TECHNICAL LOSSES CALCULATION OF 11KV KOTHAPETA FEEDER Month: MAY - 2015

Name of the Feeder : KOTHAPETA

Name of the sub station: 33/11KV B.KONERU
Name of the Section: D1, VIZIANAGARAM

1) Units sent out from the 11kv system during a particular month (30 days) = 363120

2) Average Demand = (363120)/(30\*24\*0.965) = 522.625

3) Peak Demand during the month (1.732\*11\*45) = 857.34 KVA

4) Load factor of the month =Average Demand / Peak Demand = 522.625 /(1.732\*11\*45) = 0.609589213

#### Step:-1

### 5) Distribution Transformer in the 11KV system - Number and Rating:

| No         | KVA                 | Total |
|------------|---------------------|-------|
| 0          | 250                 | 0     |
| 0          | 200                 | 0     |
| 1          | 160                 | 160   |
| 11         | 100                 | 1100  |
| 0          | 75                  | 0     |
| 0          | 63                  | 0     |
| 1          | 25                  | 25    |
| Total Tran | sformers Capacity = | 1285  |

### 6) Losses when the Demand is equal to total Transformer Capacity:

## i) Transformer Iron Losses (ISI Specification)

| No of<br>DTRS | DTR Capacity(in KVA)      | Iron Loss<br>(Watts/Each) | Per | Total |  |  |  |
|---------------|---------------------------|---------------------------|-----|-------|--|--|--|
| 0             | 250                       | 1000                      | E   | 0     |  |  |  |
| 0             | 200                       | 825                       | E   | 0     |  |  |  |
| 1             | 160                       | 650                       | E   | 650   |  |  |  |
| 11            | 100                       | 450                       | E   | 4950  |  |  |  |
| 0             | 75                        | 385                       | E   | 0     |  |  |  |
| 0             | 63                        | 350                       | Е   | 0     |  |  |  |
| 1             | 25                        | 195                       | E   | 195   |  |  |  |
|               | Total Iron Loss (Watts) = |                           |     |       |  |  |  |

ii) Transformer Copper losses:

| No of<br>DTRS | DTR Capacity(in KVA) | Copper losses<br>(Watts/Each) | Per | Total Copper<br>Losses(in Watts) |  |  |
|---------------|----------------------|-------------------------------|-----|----------------------------------|--|--|
| 0             | 250                  | 4500                          | E   | 0                                |  |  |
| 0             | 200                  | 3750                          | Ē   | 0                                |  |  |
| 1             | 160                  | 3000                          | E   | 3000                             |  |  |
| 11            | 100                  | 2000                          | E   | 22000                            |  |  |
| 0             | 75                   | 1600                          | E   | 0                                |  |  |
| 0             | 63                   | 1400                          | E   | 0                                |  |  |
| 1             | 25                   | 700                           | E   | 700                              |  |  |
|               | Total Copper Loss =  |                               |     |                                  |  |  |

11 KV side

250 KVA = 13.13 Amps ------75 KVA = 3.94 Amps 200 KVA = 10.5 Amps -----63 KVA = 3.30 Amps 160 KVA = 8.4 Amps -----50 KVA = 2.62 Amps 100 KVA = 5.25 Amps -----15 KVA = 0.79 Amps

11 KV Line Losses (as per Statement -1)

1061.0177 Watts

6(iii) Losses for 3 Conductors =

3183.053089 Watts

#### Step - II

7) Max Demand During the Month =

857.34 KVA

Total Transformer Capacity=

1285 KVA

Ratio of Max.Demand to the Transformer Capacity = Max. Demand / Total Trans Capacity=

0.667190661

i)Transformer Copper Losses ( Correct to M.D )

= Item (6) (ii) \* (Ratio )2 =

11440.18483

ii)Line Copper losses ( Corrected M.D )

= Item (6) (iii) \* (ratio)2 =

1416.915007

#### Step-III

- 8) The Losses Calculated above have to be corrected to actual loading conditions by multiplying it with loss factor
  - i) Loss Factor Calculated according to the hourly meter Readings of a typical day in the month =

0.309510031

( As per the statement-2 )

ii) Loss factor according to formulae loss factor = 0.8 (L.F)2 + 0.2\* (L.F)

0.419

L.F - Load factor (4)

Loss Factor [8(i)]

0.309510031

In Case the typical day meter readings are not available then the loss factor has to be calculated by the formulae given above.

i) Corrected transformer copper losses (actual loading condition) = 7 (i) \* L.F

3540.852

ii) Corrected line Copper losses (actual loading Conditions)= 7 (ii)\* L.F

| 9) (i) Units handled during the month (1)  | =                                  |   | 363120       |
|--|------------------------------------|---|--------------|
| Iron Losses [6 (i) ]                       | =                                  |   | 5795         |
| Copper losses [8 (i) ]                     | =                                  |   | 3540.852     |
|  | Losses [6 (i) + 8 (i) ]            | = | 9335.852     |
| (ii) For one Month                         | =Losses * 720 / 1000 =             |   | 6721.813 KWH |
| % Transformer Losses                       | = [ 9 (ii) / 9 (i) ] * 100 =       |   | 1.851        |
| (iii) 11KV Line Losses                     |                                    |   | 438.549      |
| 11KV Line losses per month                 | = 8 (ii) * 720/1000 =              |   | 315.756      |
| % 11 KV Line losses = [ Losses             | s per month / 9(i) ] *100 =        |   | 0.087        |
| 10) (i) Units handled during the month (1) | =                                  |   | 363120       |
| Units billed                               | =                                  |   | 342636       |
| Actual losses in 11KV line, Transfo        | ormer & L.T = Handled - Billed =   |   | 20484.000    |
| (ii) L.T Distribution losses               |                                    |   | 13446.431    |
| % L.T Distribution losses =[Lo             | esses per month ] / 9(i) ] * 100 - |   | 3.703        |
| %Technical +Comm Losses = [ Total lo       | oss per month]/9(i)*100            |   | 5.641110377  |

## STATEMENT: 1

11KV Line losses;

| Resistance of line = | 0.365  | Ohms/Km for 100Sq,mm    |
|----------------------|--------|-------------------------|
|                      | 0.5149 | Ohms/Km for 55Sq.mm     |
|                      | 0.9116 | Ohms/Km for 7/2.59 ACSR |
|                      | 1.37   | Ohms/Km for 7/2.11 ACSR |

| Section | Length in KM | Resistance in Ohms | Current (I) | Full load I2R<br>Watts | KVA |
|---------|--------------|--------------------|-------------|------------------------|-----|
|         | 0.01         | 0.0051             | 5.25        | 0.1419                 | 100 |
|         | 0.01         | 0.0051             | 8.4         | 0.3633                 | 160 |
|         | 0.36         | 0.1854             | 13.65       | 34.5375                | 260 |
|         | 0.05         | 0.0257             | 5.25        | 0.7096                 | 100 |
|         | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100 |
|         | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100 |
|         | 0.1          | 0.0515             | 29.4        | 44.5059                | 560 |
|         | 0.1          | 0.0515             | 34.65       | 61.8201                | 660 |
|         | 0.08         | 0.0412             | 5.25        | 1.1354                 | 100 |
|         | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100 |
|         | 0.2          | 0.1030             | 45.15       | 209.9270               | 860 |
|         | 0.11         | 0.0566             | 1.3125      | 0.0976                 | 25  |
|         | 0.1          | 0.0515 5.25 1.4192 |             | 100                    |     |
|         | 0.25         | 0.1287             | 6.5625      | 5.5437                 | 125 |

| 0.09    | 0.0463 | 51.7125 | 123.9243  | 985  |
|---------|--------|---------|-----------|------|
| 0.25    | 0.1287 | 56.9625 | 417.6774  | 1085 |
| <br>0.1 | 0.0515 | 5.25    | 1.4192    | 100  |
| 0.065   | 0.0335 | 62.2125 | 129.5363  | 1185 |
| 0.04    | 0.0206 | 5.25    | 0.5677    | 100  |
| 0.01    | 0.0051 | 67.4625 | 23.4341   | 1285 |
|         |        |         | 1061.0177 |      |

STATEMENT ;-2 Hourly Demand in Amps on the 11 KV feeder on a typical day in the month

| Time in Hours | Current (1) Amps | (Current)2 (1)2 |
|---------------|------------------|-----------------|
| 1.00          | 15               | 225             |
| 2.00          | 13               | 169             |
| 3.00          | 12               | 144             |
| 4.00          | 12               | 144             |
| 5.00          | 15               | 225             |
| 6.00          | 20               | 400             |
| 7.00          | 22               | 484             |
| 8.00          | 20               | 400             |
| 9.00          | 18               | 324             |
| 10.00         | 14               | 196             |
| 11.00         | 15               | 225             |
| 12.00         | 15               | 225             |
| 13.00         | 16               | 256             |
| 14.00         | 16               | 256             |
| 15.00         | 15               | 225             |
| 16.00         | 15               | 225             |
| 17.00         | 18               | 324             |
| 18.00         | 25               | 625             |
| 19.00         | 36               | 1296            |
| 20.00         | 28               | 784             |
| 21.00         | 27               | 729             |
| 22.00         | 27               | 729             |
| 23.00         | 24               | 576             |
| 24.00         | 21               | 441             |
|               |                  | 9627            |

Loss Factor ( L.F ) = Total 2/( Max 2 \* 24 )=

# 4.2) HISTORY SHEET OF 11KV TANK BUND FEEDER

| A. | NAME OF THE 33/11KV SUB-STATION.   | $\Longrightarrow$ | Indoor SS   |                    |                       |
|----|--|-------------------|---|--------------------|-----------------------|
| В  | NAME OF THE EHT SUB-STATION.   | $\Longrightarrow$ | EHT SS:132/33 KV Vo   | ntithadi           | S.S.Code: 021122      |
| C. | NAME OF THE FEEDER.  | $\Longrightarrow$ | 11 Tank Bund  |                    | Feeder Code :02112203 |
| D. | TYPE OF THE FEEDER   | $\Longrightarrow$ | Town  |                    |                       |
| E. | PEAK LOAD IN AMPS.   | $\Longrightarrow$ | 30 A  |                    |                       |
| F. | AVERAGE POWER FACTOR.  | $\Longrightarrow$ | 0.965   |                    |                       |
| G. | SIZE OF THE CONDUCTOR.   | $\Longrightarrow$ | 55Sqmm AAAC   |                    |                       |
| Н. | DETAILS OF ALTERNATIVE SUPPLY.   | $\Longrightarrow$ | 1. RECEIVING FROM<br>2. SENDING TO                              | 11 KV Von          | tithadi Town          |
| I. | LENGTH OF 11KV LINE.   | $\Longrightarrow$ | <ol> <li>Trunk line in KM.</li> <li>Spur Line in KM.</li> </ol> | 1.22 KM<br>0.57 KM |                       |
| J. | LENGTH OF LT LINE.   | $\Longrightarrow$ | <ol> <li>Trunk line in KM.</li> <li>Spur Line in KM.</li> </ol> | 3.1 KM<br>4.2 KM   |                       |
| K. | % TECHNICAL LOSSES.  | $\Longrightarrow$ | 2.40%   |                    |                       |
|    | % REGULATIONS.   | $\Longrightarrow$ | 0.64%   |                    |                       |
|    | Names of the villages being fed from this f  | eeder ( Fo        | or Town/MHQ feeder onl  | v)f :              |                       |
|    | Names of all the Sections being fed from   | •                 | •   | , ,                | Town                  |
|    | :  | iilis leede       | l .   |                    | D1                    |
|    | No of Distributions being fed from this fee Wheteher all sections and distributions have |                   | in DAA Data, and all sam  |                    | 8                     |
|    | indexed:   | ve Codes          | III FAA Data and all con  | isumers are        | Yes                   |

## No. of the DTRs - Capacity wise :

| Capacity    | 315 | 250 | 160 | 100 | 75 | 63 | 25 | Total No. | Total<br>Capacity |
|-------------|-----|-----|-----|-----|----|----|----|-----------|-------------------|
| No. of DTRs | 0   | 1   | 0   | 8   | 0  | 0  | 0  | 9         | 1050              |

|        | Category wise consumers &Sales ( Present) |       |       |      |     |   |      |      |    |        |
|--------|---|-------|-------|------|-----|---|------|------|----|--------|
|        | Cat.                                      | I     | 11    | 111  | IV  | V | VI   | VII  | HT | TOTAL  |
| Mai.15 | No. of Scs.                               | 977   | 404   | 13   | 3   | 0 | 7    | 10   | 0  | 1414   |
|        | Sales                                     | 83384 | 88546 | 8161 | 184 | 0 | 1723 | 2646 | 0  | 184644 |
|        | Sp.Con                                    | 85    | 219   | 628  | 61  | 0 | 246  | 265  | 0  | 131    |


## II LOSSES THIS YEAR:

| SI.No. | Month  | Input to 11KV<br>Feeder | 11KV Direct<br>Sales | Metered<br>Sales | Connected load in AGL services | AGL.Sales | Assessed<br>Units | Total<br>Sales | Loss  | % Loss for the month |
|--------|--------|-------------------------|----------------------|------------------|--------------------------------|-----------|-------------------|----------------|-------|----------------------|
| 1      | 2      | 3                       | 4                    | 5                | 6                              | 7         | 8                 | 8              | 9     | 10                   |
| 1      | Jän.15 | 131600                  | 0                    | 124196           | 0                              | 0         | 0                 | 124196         | 7404  | 5.63                 |
| 2      | Feb.15 | 127200                  | 0                    | 120128           | 0                              | 0         | 0                 | 120128         | 7072  | 5.56                 |
| 3      | Mär.15 | 178400                  | 0                    | 168305           | 0                              | 0         | 0                 | 168305         | 10095 | 5.66                 |
| 4      | Apr.15 | 227800                  | 0                    | 216155           | 0                              | 0         | 0                 | 216155         | 11645 | 5.11                 |
| 5      | Mai.15 | 193600                  | 0                    | 183855           | 0                              | 0         | 0                 | 183855         | 9745  | 5.03                 |

FORMATE- 5 TOTAL AGRICULATURAL SERVICES UNDER FEEDER:

|   |       |                  |                              |                                   |                                 | TO CIVILI                                |                        | F   |
|---|-------|------------------|------------------------------|-----------------------------------|---------------------------------|--|------------------------|---|
| L | s.No. | Catgory          | Details of Agl Consumers     |                                   |                                 |  |                        | continos                                    |
|   |       |                  | No of<br>metered<br>services | Total HP of<br>metred<br>services | No of un<br>metered<br>services | total HP of<br>Un<br>metered<br>services | Assesed<br>Agrl. Sales | services<br>availing 24<br>Hours<br>supply. |
| [ | 1     | IT assesses.     |                              |                                   |                                 |  |                        |   |
|   | 2     | Corporate.       |                              |                                   | ·                               | L  |                        |   |
|   | 3     | Tatkal.          |                              | 1                                 |                                 |  |                        |   |
|   | 4     | Other paying Scs |                              | 1                                 | NIL                             |  |                        |   |
|   | 5     | Free.            |                              |                                   |                                 |  |                        |   |
|   | 6     | Total.           |                              |                                   |                                 |  |                        |   |

# 4.2.1) 11KV Tank Bund Feeder Sketch



33/11 KV INDOOR S.S.

# 4.2.2 ) 11KV Tank Bund Feeder Regulation Chart

| 0.05 | 0.25 | 0.2 | 0.3 | 0.1 | 0.1 | 0.2 |
|------|------|-----|-----|-----|-----|-----|
| 100  | 100  | 100 | 450 | 100 | 100 | 100 |

33 / 11kv Indoor SS

1 X 5 MVA

| 1050 | 950 | 850 | 750 | 300 | 200 | 100 |
|------|-----|-----|-----|-----|-----|-----|
| 1    | 1   |     |     |     |     | 1   |

|       | MOMEN | ITS   |        |  |
|-------|-------|-------|--------|--|
| SI.No | KVA   | KM    | Total  |  |
| 1     | 1050  | 0.05  | 52.50  | HT Regulation                            |
| 2     | 950   | 0.25  | 237.50 | <u>0.08566</u> <u>750.00</u> <b>0.64</b> |
| 3     | 850   | 0.20  | 170.00 | 100.00                                   |
| 4     | 750   | 0.30  | 225.00 |  |
| 5     | 300   | 0.10  | 30.00  | 0.64%                                    |
| 6     | 200   | 0.10  | 20.00  | Hence, Satisfactory                      |
| 7     | 100   | 0.15  | 15.00  |  |
|       |       | TOTAL | 750.00 |  |

## 4.2.3) TECHNICAL LOSSES CALCULATION OF 11KV TANK BUND FEEDER

Month: MAY -2015

Name of the Feeder : Tank bund feeder

Name of the sub station: 33/11KV Indoor Sub Station

Name of the Section : D1, VIZIANAGARAM

1) Units sent out from the 11kv system during a particular month (30 days) = 193600

2) Average Demand = (193600) / (30\*24\*0.965) = 278.641

3) Peak Demand during the month (1.732\*11\*30) = 571.56 KVA

4) Load factor of the month =Average Demand / Peak Demand = 278.641 /(1.732\*11\*30) = 0.48751021

#### Step:-1

## 5) Distribution Transformer in the 11KV system - Number and Rating:

| No         | KVA                 | Total |
|------------|---------------------|-------|
| 1          | 250                 | 250   |
| 0          | 200                 | 0     |
| 0          | 160                 | 0     |
| 8          | 100                 | 800   |
| 0          | 75                  | 0     |
| 0          | 63                  | 0     |
| 0          | 25                  | 0     |
| Total Tran | sformers Capacity = | 1050  |

#### 6) Losses when the Demand is equal to total Transformer Capacity:

#### i) Transformer Iron Losses (ISI Specification)

| No of | DTR Capacity(in   | Iron Loss    |     |       |
|-------|---|--------------|-----|-------|
| DTRS  | KVA)  | (Watts/Each) | Per | Total |
| 1     | 250   | 1000         | Е   | 1000  |
| 00    | 200   | 825          | E   | 0     |
| 0     | 160   | 650          | E   | 0     |
| 8     | 100   | 450          | E   | 3600  |
| 0     | 75  | 385          | E   | 0     |
| 0     | 63  | 350          | E   | 0     |
| 0     | 25  | 195          | E   | 0     |
|       | (watts/Each)  1 250 1000 E  200 825 E  1 160 650 E  3 100 450 E  0 75 385 E  0 63 350 E |              |     | 4600  |

ii) Transformer Copper losses:

| No of<br>DTRS | DTR Capacity(in KVA)                 | Copper losses<br>(Watts/Each) | Per | Total Copper<br>Losses(in Watts) |
|---------------|--------------------------------------|-------------------------------|-----|----------------------------------|
| 1             | 250                                  | 4500                          | E   | 4500                             |
| 0             | 200                                  | 3750                          | E   | 0                                |
| 0             | 160                                  | 3000                          | E   | 0                                |
| 8             | 100                                  | 2000                          | E   | 16000                            |
| 0             | 75                                   | 1600                          | E   | 0                                |
| 0             | 63                                   | 1400                          | Е   | 0                                |
| 0             | 25                                   | 700                           | E   | 0                                |
|               | 100 2000 E<br>75 1600 E<br>63 1400 E |                               |     | 20500                            |

#### 11 KV side

250 KVA = 13.13 Amps ------75 KVA = 3.94 Amps 200 KVA = 10.5 Amps -----63 KVA = 3.30 Amps 160 KVA = 8.4 Amps -----50 KVA = 2.62 Amps 100 KVA = 5.25 Amps -----15 KVA = 0.79 Amps

11 KV Line Losses (as per Statement -1) 924.4092 Watts 6(iii) Losses for 3 Conductors = 2773.227546 Watts

#### Step - II

7) Max Demand During the Month =

571.56 KVA

Total Transformer Capacity=

1050 KVA

Ratio of Max.Demand to the Transformer Capacity = Max. Demand / Total Trans Capacity=

0.544342857

i)Transformer Copper Losses (Correct to M.D.)

= Item (6) (ii) \* ( Ratio )2 =

6074.337496

ii)Line Copper losses (Corrected M.D)

= Item (6) (iii) \* (ratio)2 =

821.7326861

#### Step-III

8) The Losses Calculated above have to be corrected to actual loading conditions by multiplying it with loss factor

i) Loss Factor Calculated according to the hourly meter Readings of a typical day in the month =

0.275277489

( As per the statement-2 )

ii) Loss factor according to formulae loss factor = 0.8 (L.F)2 + 0.2\* (L.F)

0.288

L.F - Load factor (4)

Loss Factor [8(i)]

0,275277489

In Case the typical day meter readings are not available then the loss factor has to be calculated by the formulae given above.

i) Corrected transformer copper losses (actual loading condition) = 7 (i) \* L.F

1672.128

ii) Corrected line Copper losses (actual loading Conditions)= 7 (ii)\* L.F

| 9) (i) Units handled during the month (1) Iron Losses [6 (i) ] Copper losses [8 (i) ] | =<br>=<br>=<br>Losses [6 (i) + 8 (i) ] | = | 193600<br>4600<br>1672.128<br>6272.128 |
|---|--|---|--|
| (ii) For one Month  | =Losses * 672 / 1000 =                 |   | 4515.932 KWH                           |
| % Transformer Losses  | = [ 9 (ii) / 9 (i) ] * 100 =           |   | 2.333                                  |
| (iii) 11KV Line Losses  |  |   | 226.205                                |
| 11KV Line losses per month  | = 8 (ii) * 720/1000 =                  |   | 162.867                                |
| % 11 KV Line losses = [ Losses  | s per month / 9(i) ] *100 =            |   | 0.084                                  |
| 10) (i) Units handled during the month (1)  |  |   | 193600                                 |
| Units billed  | =                                      |   | 183855                                 |
| Actual losses in 11KV line, Transfo   | ormer & L.T = Handled - Billed =       |   | 9745.000                               |
| (ii) L.T Distribution losses  |  |   | 5066.200                               |
| % L.T Distribution losses =[Lo  | sses per month ] / 9(i) ] * 100 -      |   | 2.617                                  |
| %Technical +Comm Losses = [ Total lo  | ss per month]/9(i)*100                 |   | 5.03357438                             |

## 11KV Line losses;

STATEMENT: 1

| Resistance of line = | 0.365  | Ohms/Km for 100Sq,mm    |
|----------------------|--------|-------------------------|
|                      | 0.5149 | Ohms/Km for 55Sq.mm     |
|                      | 0.9116 | Ohms/Km for 7/2.59 ACSR |
|                      | 1.37   | Ohms/Km for 7/2.11 ACSR |

| Section | Length in KM | Resistance in Ohms | Current (I) | Full load I2R<br>Watts | KVA  |
|---------|--------------|--------------------|-------------|------------------------|------|
|         | 0.015        | 0.0077             | 13.125      | 1.3305                 | 250  |
|         | 0.15         | 0.0772             | 18.375      | 26.0777                | 350  |
|         | 0.1          | 0.0515             | 23.625      | 28.7387                | 450  |
|         | 0.15         | 0.0772             | 5.25        | 2.1288                 | 100  |
|         | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100  |
|         | 0.1          | 0.0515             | 10.5        | 5.6768                 | 200  |
|         | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100  |
|         | 0.1          | 0.0515             | 15.75       | 12.7727                | 300  |
|         | 0.3          | 0.1545             | 39.375      | 239.4888               | 750  |
|         | 0.07         | 0.0360             | 5.25        | 0.9934                 | 100  |
|         | 0.2          | 0.1030             | 44.625      | 205.0734               | 850  |
|         | 0.05         | 0.0257             | 5.25        | 0.7096                 | 100  |
|         | 0.25         | 0.1287             | 49.875      | 320.2054               | 950  |
|         | 0.01         | 0.0051             | 5.25        | 0.1419                 | 100  |
|         | 0.05         | 0.0257             | 55.125      | 78.2330                | 1050 |
|         |              |                    |             | 924.4092               |      |

40

STATEMENT :-2 Hourly Demand in Amps on the 11 KV feeder on a typical day in the month

| Time in Hours | Current (1) Amps | (Current)2 (1)2 |
|---------------|------------------|-----------------|
| 1.00          | 6                | 36              |
| 2.00          | 6                | 36              |
| 3.00          | 6                | 36              |
| 4.00          | 6                | 36              |
| 5.00          | 7                | 49              |
| 6.00          | 9                | 81              |
| 7.00          | 13               | 169             |
| 8.00          | 10               | 100             |
| 9.00          | 8                | 64              |
| 10.00         | 14               | 196             |
| 11.00         | 18               | 324             |
| 12.00         | 19               | 361             |
| 13.00         | 20               | 400             |
| 14.00         | 18               | 324             |
| 15.00         | 17               | 289             |
| 16.00         | 16               | 256             |
| 17.00         | 20               | 400             |
| 18.00         | 27               | 729             |
| 19.00         | 27               | 729             |
| 20.00         | 31               | 961             |
| 21.00         | 22               | 484             |
| 22.00         | 12               | 144             |
| 23.00         | 9                | 81              |
| 24.00         | 8                | 64              |
|               |                  | 6349            |

Loss Factor ( L.F ) = Total 2/( Max 2 \* 24 )=

# 4.3 ) HISTORY SHEET OF 11 KV GAJULAREGA FEEDER

| A. | NAME OF THE 33/11KV SUB-STATION.   | $\Longrightarrow$ | B.Koneru  |                                |            |              |  |  |
|----|--|-------------------|---|--------------------------------|------------|--------------|--|--|
| В  | NAME OF THE EHT SUB-STATION.   | $\Longrightarrow$ | EHT SS:132/33 KV Vont   | tithadi                        | S.S.Code:  | 021111       |  |  |
| C. | NAME OF THE FEEDER.  | $\Longrightarrow$ | 11 KV Gajula Rega   |                                | Feeder Cod | de :02111102 |  |  |
| D. | TYPE OF THE FEEDER   | $\Longrightarrow$ | Town  |                                |            |              |  |  |
| E. | PEAK LOAD IN AMPS.   | $\Longrightarrow$ | 68A   |                                |            |              |  |  |
| F. | AVERAGE POWER FACTOR.  | $\Longrightarrow$ | 0.965   |                                |            |              |  |  |
| G. | SIZE OF THE CONDUCTOR.   | $\Longrightarrow$ | 55Sqmm AAAC   |                                |            |              |  |  |
| Н. | DETAILS OF ALTERNATIVE SUPPLY.   | $\Longrightarrow$ | 1. RECEIVING FROM<br>2. SENDING TO                              | 11 KV Butchanna<br>Gajula Rega | Koneru     |              |  |  |
| l. | LENGTH OF 11KV LINE.   | $\Longrightarrow$ | <ol> <li>Trunk line in KM.</li> <li>Spur Line in KM.</li> </ol> | 8.2 KM<br>5.0 KM               |            |              |  |  |
| J. | LENGTH OF LT LINE.   | $\Longrightarrow$ | <ol> <li>Trunk line in KM.</li> <li>Spur Line in KM.</li> </ol> | 25.05 KM<br>20.2 KM            |            |              |  |  |
| K. | % TECHNICAL LOSSES.  | $\Longrightarrow$ | 3.70%   | 20.2 1(1)                      |            |              |  |  |
|    | % REGULATIONS.   | $\Longrightarrow$ | 7.53%   |                                |            |              |  |  |
|    | Names of the villages being fed from this feeder only)f:                             | feeder (For       | Town/MHQ  |                                |            | Town         |  |  |
|    | Names of all the Sections being fed  | d from this fe    | eeder:  |                                |            | D1           |  |  |
|    | No of DTRs   |                   |   |                                |            |              |  |  |
|    | Wheteher all sections and distributions hav all consumers are inde No. of the DTRs - |                   | PAA Data and  |                                |            | 51<br>Yes    |  |  |

No. of the DTRs Capacity wise :

| Capacity    | 160 | 100 | 75 | 63 | 50 | 25 | 250 | Total No. | Total<br>Capacity |
|-------------|-----|-----|----|----|----|----|-----|-----------|-------------------|
| No. of DTRs | 2   | 38  | 1  | 6  | 1  | 3  | 0   | 51        | 4698              |

## Category wise consumers &Sales ( Present)

|        | Cat.        | l      | 11    | III   | IV | ٧   | VI   | VII  | HT | TOTAL    |
|--------|-------------|--------|-------|-------|----|-----|------|------|----|----------|
| Mai.15 | No. of Scs. | 4676   | 270   | 60    | 0  | 4   | 22   | 23   | 0  | 5055     |
|        | Sales       | 441247 | 54251 | 79895 | 0  | 806 | 8412 | 1790 | 0  | 586401   |
|        | Sp.Con      | 94     | 201   | 1332  | 0  | 202 | 382  | 78   | 0  | 116.0042 |

LOSSES THIS II

YEAR:

| SI.No. | Month  | Input to<br>11KV<br>Feeder | 11KV<br>Direct<br>Sales | Metered<br>Sales | Connected<br>load in<br>AGL<br>services | AGL.Sales | Assessed Units | Total Sales | Loss  | % Loss<br>for the<br>month |
|--------|--------|----------------------------|-------------------------|------------------|---|-----------|----------------|-------------|-------|----------------------------|
| 1      |        | 3                          | 4                       | 5                | 6                                       | 7         | 8              | 8           | 9     | 10                         |
| 1      | Jän.15 | 456320                     | 0                       | 429200           | 11                                      | 565       | 0              | 429765      | 26555 | 5.82                       |
| 2      | Feb.15 | 524240                     | 0                       | 487474           | 11                                      | 451       | 0              | 487925      | 36315 | 6.93                       |
| 3      | Mär.15 | 553480                     | 0                       | 522035           | 11                                      | 568       | 0              | 522603      | 30877 | 5.58                       |
| 4      | Apr.15 | 633520                     | 0                       | 595011           | 11                                      | 715       | 0              | 595726      | 37794 | 5.97                       |
| 5      | Mai.15 | 624080                     | 0                       | 585595           | 11                                      | 806       | 0              | 586401      | 37679 | 6.04                       |

FORMATE- 5 TOTAL AGRICULATURAL SERVICES UNDER FEEDER:-

| s.No. | Catgory          | Details of<br>Agl<br>Consumers |                                   |                                 | IN LE GERATO                          |                        | services availing<br>24 Hours supply. |
|-------|------------------|--------------------------------|-----------------------------------|---------------------------------|---------------------------------------|------------------------|---------------------------------------|
|       |                  | No of<br>metered<br>services   | Total HP<br>of metred<br>services | No of un<br>metered<br>services | total HP of<br>Un metered<br>services | Assesed<br>Agrl. Sales |                                       |
| 1     | IT assesses.     |                                |                                   |                                 |                                       |                        |                                       |
| 2     | Corporate.       |                                |                                   |                                 |                                       |                        |                                       |
| 3     | Tatkal.          | 3                              | 11                                | 0                               |                                       |                        |                                       |
| 4     | Other paying Scs |                                |                                   |                                 | <del></del>                           |                        |                                       |
| 5     | Free.            | 1                              | 3                                 | 0                               |                                       |                        |                                       |
| 6     | Total.           |                                |                                   |                                 |                                       |                        |                                       |

4.3.1) 11 KV GAJULAREGA FEEDER SKETCH SS-234 0.2 33/11KV S.S 100KVA 38 NO. SS-241 0.61 100 SS-239 160KVA 2 NO. 100 SS-256 63 0.08 0.2 SS-118 0.2 100 SS-84 SS-164 0.1 0.28 75KVA 1 NO. 0.1 0.09 0.5 0.5 0.05 0.01 50KVA 1 NO. SS-266 SS-281 SS-280 100 0.5 63KVA 6 NO. SS-185 0.08 100 100 SS-250 25KVA 3 NO. 100 SS-284 SS-187 SS-44 63 100 SS-98 75 100 0.05 SS-233 160 SS-287 0.03 SS-268 100 SS-183 25 0.09 /\SS-16 100 0.12 0.45 SS-255 0.12 SS-279 63 SS-228 0.23 100 100 SS-119 0.05 100 0.22 0.6 SS-270 0.07 0.13 0.5 SS-245 0.03 100 SS-5 0.05 0.315 SS-231 SS-139 SS-101 SS-265 100 100 SS-29 SS-109 160 SS-125 100 100 0.14 100 0.51 SS-17 SS-253 0.11 100 SS-299 SS-294 100 SS-165 S 33/11 KV B.KONERU S.S. SS-267 SS-297 100 100 100 100 SS-296 100 SS-293 SS-290 100 SS-295 SS-258 63

44

## 4.3.2 ) 11KV Gajularega Feeder Regulation Chart

| 0.11 | 0.51 | 0.60 | 0.10 | 0.10 | 0.10 | 0.12 | 0.45 | 0.67 | 0.20 | 0.50 | 0.50 | 0.30 | 0.20 | 0.10 | 0.10 | 0.10 | 0.20 |
|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|
| 100  | 648  | 1426 | 100  | 513  | 100  | 263  | 225  | 100  | 263  | 260  | 100  | 100  | 100  | 100  | 100  | 100  | 100  |

33 / 11kv

14

15

16

17

18

500 0.20 100.00

0.10

0.10

0.10

0.20

TOTAL 8795.59

400

300

200

100

40.00

30.00

20.00

| 33 / 11KV   |      |      |         |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
|-------------|------|------|---------|----------------------|-------|----------------|------|------|------|------|-----|-----|-----|-----|-----|-----|-----|-----|
| B.Koneru SS |      |      |         |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 1 X 8 MVA   | 4698 |      | 3950    | 2524                 | 2424  | 1911           | 1811 | 1548 | 1323 | 1223 | 960 | 700 | 600 | 500 | 400 | 300 | 200 | 100 |
| N           | OMEN | rs   |         |                      |       | -              |      |      |      |      |     | -   |     |     |     |     |     |     |
| SI.No       | KVA  | KM   | Total   |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 1           | 4698 | 0.11 | 516.78  |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 2           | 4598 | 0.51 | 2344.98 | HT<br>Regula<br>tion | 0.086 | <u>8795.59</u> | 7.53 |      |      |      |     |     |     |     |     |     |     |     |
| 3           | 3950 | 0.60 | 2370.00 |                      | 10    | 00.00          |      |      |      |      |     |     |     |     |     |     |     |     |
| 4           | 2524 | 0.10 | 252.40  |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 5           | 2424 | 0.10 | 242.40  | Hen<br>Satisfa       |       | 7.53%          |      |      |      |      |     |     |     |     |     |     |     |     |
| 6           | 1911 | 0.10 | 191.10  |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 7           | 1811 | 0.12 | 217.32  |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 8           | 1548 | 0.20 | 309.60  |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 9           | 1323 | 0.67 | 886.41  |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 10          | 1223 | 0.20 | 244.60  |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 11          | 960  | 0.50 | 480.00  |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 12          | 700  | 0.50 | 350.00  |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |
| 13          | 600  | 0.30 | 180.00  |                      |       |                |      |      |      |      |     |     |     |     |     |     |     |     |

# 4.3.3)TECHNICAL LOSSES CALCULATIONS OF 11KV GAJULAREGA FEEDER Month: MAY 2015

Name of the Feeder: Gajularega

Name of the sub station: B.KONERU

Name of the Section: D1,

1) Units sent out from the 11kv system during a particular month ( 30 days )= 624080

2) Average Demand = (624080)/(30\*24\*0.965) = 898.215

3) Peak Demand during the month (1.732\*11\*68) = 1295.536 KVA

4) Load factor of the month = Average Demand / Peak Demand = 898.215 /(1.732\*11\*68) = 0.693315596

#### Step:-1

5) Distribution Transformer in the 11KV system - Number and Rating:

| No         | KVA                  | Total |
|------------|----------------------|-------|
| 0          | 315                  | 0     |
| 0          | 250                  | 0     |
| 2          | 160                  | 320   |
| 38         | 100                  | 3800  |
| 1          | 75                   | 75    |
| 6          | 63                   | 378   |
| 1          | 50                   | 50    |
| 3          | 25                   | 75    |
| 0          | 15                   | 0     |
| Total Trai | nsformers Capacity = | 4698  |

6) Losses when the Demand is equal to total Transformer Capacity .

i) Transformer Iron Losses (ISI Specification)

| No of<br>DTRS | DTR Capacity(in KVA) | Iron Loss(Watts/Each) | Per | Total |
|---------------|----------------------|-----------------------|-----|-------|
| 0             | 315                  | 1200                  | Е   | 0     |
| 0             | 250                  | 1000                  | E   | 0     |
| 2             | 160                  | 650                   | E   | 1300  |
| 38            | 100                  | 450                   | E   | 17100 |
| 1             | 75                   | 385                   | E   | 385   |
| 6             | 63                   | 350                   | E   | 2100  |
| 1             | 50                   | 130                   | E   | 130   |
| 3             | 25                   | 195                   | E   | 585   |
| 0             | 15                   | 60                    | E   | 0     |
|               | Total Iro            | n Loss (Watts) =      |     | 21600 |

ii) Transformer Copper losses

| No of | DTR Capacity(in | Copper             | Don | Total Copper     |
|-------|-----------------|--------------------|-----|------------------|
| DTRS  | KVA)            | losses(Watts/Each) | Per | Losses(in Watts) |
| 0     | 315             | 5700               | E   | 0                |
| 0     | 250             | 4500               | E   | 0                |
| 2     | 160             | 3000               | E   | 6000             |
| 38    | 100             | 2000               | E   | 76000            |
| 1     | 75              | 1600               | E   | 1600             |
| 6     | 63              | 1400               | E   | 8400             |
| 1     | 50              | 880                | E   | 880              |
| 3     | 25              | 700                | E   | 2100             |
| 0     | 15              | 600                | E   | 0                |
|       | Total           | Copper Loss =      |     | 94980            |

#### 11 KV side

315 KVA = 16.54 Amps -----75 KVA =3.94 Amps 250 KVA = 13.13 Amps ------63 KVA =3.30 Amps 160 KVA = 8.4 Amps ------50 KVA = 2.62 Amps 100 KVA = 5.25 Amps -----15 KVA = 0.79 Amps

11 KV Line Losses (as per Statement -1) =21799.8691 6(iii) Losses for 3 Conductors =

43430.7458 Watts 130292.2374 Watts

#### Step - II

7) Max Demand During the Month =

1295.536 KVA

Total Transformer Capacity=

4698 KVA

Ratio of Max.Demand to the Transformer Capacity = Max. Demand / Total Trans Capacity=

7222.792052

0.275763

i)Transformer Copper Losses ( Correct to M.D )

= Item (6) (ii) \* ( Ratio )2 =

ii)Line Copper losses (Corrected M.D)

= Item (6 ) ( iii ) \* ( ratio )2 =

| Step-III  8) The Losses Calculated above have to be owith loss factor                                 | corrected to actual loading conditions by mu   | Itiplying it     |
|---|--|------------------|
| <ul> <li>i) Loss Factor Calculated according to the ho</li> <li>( As per the statement-2 )</li> </ul> | urly meter Readings of a typical day in the r  | month = 0.646343 |
| ii) Loss factor according to formulae loss fact L.F - Load factor (4)                                 | or = 0.8 (L.F)2 + 0.2* ( L.F )                 | 0.385            |
| Loss Factor [8(i)]  | =  | 0.646342593      |
| In Case the typical day meter readings are no formulae given above.                                   | ot available then the loss factor has to be ca | Iculated by the  |
| i)Corrected transformer copper losses (actua  | I loading condition) = 7 (i) * L.F =           | 4668.398         |
| ii)Corrected line Copper losses ( actual loadir   |  | 6404.043         |
|   | , ,,   |                  |
| <ol><li>(i) Units handled during the month (1)</li></ol>  | =  | 624080           |
| Iron Losses [6 (i) ]  | =  | 21600            |
| Copper losses [8 (i) ]  | =  | 4668.398         |
|   | Losses [6 (i) + 8 (i) ]                        | = 26268.398      |
| (ii) For one Month  | Leann  | 10010 017 10111  |
| (ii) For one Month = % Transformer Losses   | Losses * 720 / 1000 =                          | 18913.247 KWH    |
| % Transformer Losses  | = [ 9 (ii) / 9 (i) ] * 100 =                   | 3.031            |
| (iii) 11KV Line Losses  |  | 6404.043         |
| 11KV Line losses per month  | = 8 (ii) * 720/1000 =                          | 4610.911 KWH     |
|   | er month / 9(i) ] *100 =                       | 0.739            |
| 10) (i) Units handled during the month (1)  | =  | 624080           |
| Units billed  | =  | 586401           |
| Actual losses in 11KV line, Transformer   | & L.T = Handled - Billed =                     | 37679            |
| (iv) L.T Distribution losses  |  | 14154.842        |
| % L.T Distribution losses =[Losses per  | month]/9(i)]*100-                              | 2.268            |
| %Technical +Comm Losses = [ Total loss  | per month]/9(i)*100                            | 6.03752724       |

# STATEMENT : 1

11KV Line losses;

Resistance of line =

0.365 Ohms/Km for 100Sq,mm 0.5149 Ohms/Km for 55Sq.mm 0.9116 Ohms/Km for 7/2.59 ACSR 1.37 Ohms/Km for 7/2.11 ACSR

| Section                               | Length in KM | Resistance in Ohms | Current (I) | Full load I2R<br>Watts | KVA  |
|---------------------------------------|--------------|--------------------|-------------|------------------------|------|
|                                       | 0.2          | 0.1030             | 5.25        | 2.8384                 | 100  |
|                                       | 0.1          | 0.0515             | 15.75       | 12.7727                | 300  |
|                                       | 0.05         | 0.0257             | 5.25        | 0.7096                 | 100  |
|                                       | 0.1          | 0.0515             | 21          | 22.7071                | 400  |
|                                       | 0.1          | 0.0515             | 26.25       | 35.4798                | 500  |
|                                       | 0.01         | 0.0051             | 5.25        | 0.1419                 | 100  |
|                                       | 0.2          | 0.1030             | 31.5        | 102.1819               | 600  |
|                                       | 0.2          | 0.1030             | 5.25        | 2.8384                 | 100  |
| · · · · · · · · · · · · · · · · · · · | 0.3          | 0.1545             | 36.75       | 208.6214               | 700  |
| <del></del>                           | 0.5          | 0.2575             | 5.25        | 7.0960                 | 100  |
|                                       | 0.5          | 0.2575             | 42          | 454.1418               | 800  |
|                                       | 0.08         | 0.0412             | 8.4         | 2.9065                 | 160  |
| -                                     | 0.28         | 0.1442             | 5.25        | 3.9737                 | 100  |
|                                       | 0.5          | 0.2575             | 50.4        | 653.9642               | 960  |
|                                       | 0.09         | 0.0463             | 3.3075      | 0.5069                 | 63   |
|                                       | 0.01         | 0.0051             | 10.5        | 0.5677                 | 200  |
|                                       | 0.2          | 0.1030             | 64.2075     | 424.5457               | 1223 |
|                                       | 0.55         | 0.2832             | 69.4575     | 1366.2302              | 1323 |
|                                       | 0.06         | 0.0309             | 5.25        | 0.8515                 | 100  |
|                                       | 0.14         | 0.0721             | 1.3125      | 0.1242                 | 25   |
|                                       | 0.1          | 0.0515             | 6.5625      | 2.2175                 | 125  |
|                                       | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100  |
|                                       | 0.22         | 0.1133             | 11.8125     | 15.8063                | 225  |
|                                       | 0.45         | 0.2317             | 81.27       | 1530.3682              | 1548 |
|                                       | 0.07         | 0.0360             | 3.3075      | 0.3943                 | 63   |
|                                       | 0.03         | 0.0154             | 5.25        | 0.4258                 | 100  |
|                                       | 0.01         | 0.0051             | 5.25        | 0.1419                 | 100  |
|                                       | 0.01         | 0.0051             | 13.8075     | 0.9816                 | 263  |
|                                       | 0.12         | 0.0618             | 95.0775     | 558.5469               | 1811 |
|                                       | 0.1          | 0.0515             | 100.3275    | 518.2781               | 1911 |
|                                       | 0.08         | 0.0412             | 3.3075      | 0.4506                 | 63   |
|                                       | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100  |
|                                       | 0.09         | 0.0463             | 8.5575      | 3.3936                 | 163  |
|                                       | 0.1          | 0.0515             | 13.8075     | 9.8164                 | 263  |
|                                       | 0.05         | 0.0257             | 17.745      | 8.1067                 | 338  |
|                                       | 0.09         | 0.0463             | 1.3125      | 0.0798                 | 25   |
|                                       | 0.03         | 0.0154             | 19.0575     | 5.6102                 | 363  |

| Δ  |
|----|
|    |
| ₩. |
|    |

| <br>     |        | · · · · · · · · · · · · · · · · · · · | 43430.7458 |      |
|----------|--------|---------------------------------------|------------|------|
| <br>0.11 | 0.0566 | 246.645                               | 3445.5631  | 4698 |
| 0.1      | 0.0515 | 5.25                                  | 1.4192     | 100  |
| <br>0.51 | 0.2626 | 241.395                               | 15302.0497 | 4598 |
| 0.1      | 0.0515 | 10.5                                  | 5.6768     | 200  |
| 0.32     | 0.1648 | 20.37                                 | 68.3683    | 388  |
| 0.05     | 0.0257 | 5.25                                  | 0.7096     | 100  |
| 0.05     | 0.0257 | 15.12                                 | 5.8857     | 288  |
| 0.13     | 0.0669 | 5.25                                  | 1.8450     | 100  |
| 0.23     | 0.1184 | 1.3125                                | 0.2040     | 25   |
| 0.04     | 0.0206 | 3.3075                                | 0.2253     | 63   |
| 0.6      | 0.3089 | 210                                   | 13624.2540 | 400  |
| 0.3      | 0.1545 | 74.865                                | 865.7685   | 142  |
| <br>0.1  | 0.0515 | 69.615                                | 249.5333   | 132  |
| <br>0.5  | 0.2575 | 64.365                                | 1066.5776  | 122  |
| 0.2      | 0.1030 | 48.615                                | 243.3848   | 926  |
| 0.1      | 0.0515 | 43.365                                | 96.8281    | 826  |
| 0.6      | 0.3089 | 40.0575                               | 495.7261   | 763  |
| 0.3      | 0.1545 | 19.0575                               | 56.1017    | 363  |
| 0.3      | 0.1545 | 21                                    | 68.1213    | 400  |
| 0.2      | 0,1030 | 15.75                                 | 25.5455    | 300  |
| 0.1      | 0.0515 | 5.25                                  | 1.4192     | 100  |
| 0.1      | 0.0515 | 5.25                                  | 1.4192     | 100  |
| 0.1      | 0.0515 | 5.25                                  | 1.4192     | 100  |
| 0.1      | 0.0515 | 135.135                               | 940.2830   | 257  |
| <br>0.1  | 0.0515 | 129.885                               | 868.6421   | 247  |
| <br>0.09 | 0.0463 | 5.25                                  | 1.2773     | 100  |
| <br>0.1  | 0.0515 | 24.3075                               | 30.4231    | 463  |
| 0.1      | 0.0515 | 5.25                                  | 1.4192     | 100  |

STATEMENT:-2
Hourly Demand in Amps on the 11 KV feeder on a typical day in the month

| Time in Hours | Current (1) Amps | (Current)2 (1)2 |
|---------------|------------------|-----------------|
| 1.00          | 47               | 2209            |
| 2.00          | 45               | 2025            |
| 3.00          | 41               | 1681            |
| 4.00          | 37               | 1369            |
| 5.00          | 35               | 1225            |
| 6.00          | 37               | 1369            |
| 7.00          | 38               | 1444            |
| 8.00          | 47               | 2209            |
| 9.00          | 46               | 2116            |
| 10.00         | 46               | 2116            |
| 11.00         | 46               | 2116            |
| 12.00         | 48               | 2304            |
| 13.00         | 48               | 2304            |
| 14.00         | 48               | 2304            |
| 15.00         | 48               | 2304            |
| 16.00         | 48               | 2304            |
| 17.00         | 46               | 2116            |
| 18.00         | 50               | 2500            |
| 19.00         | 58               | 3364            |
| 20.00         | 58               | 3364            |
| 21.00         | 68               | 4624            |
| 22.00         | 58               | 3364            |
| 23.00         | 53               | 2809            |
| 24.00         | 48               | 2304            |
|               |                  | 55844           |

Loss Factor ( L.F ) = Total 2/( Max 2 \* 24 )=

# 4.4) HISTORY SHEET OF 11KV B.Koneru TOWN FEEDER

|    | <u> </u>                                      | <u> </u>          | OI TIICT DIICOITOIT   | - 1 - 11111                      |          |                |
|----|---|-------------------|---|----------------------------------|----------|----------------|
|    | 1   |                   |   |                                  |          |                |
| A. | NAME OF THE 33/11KV SUB-STATION.              | $\Rightarrow$     | B.koneru  |                                  |          |                |
| В  | NAME OF THE EHT SUB-STATION.                  | $\Longrightarrow$ | EHT SS:132/33 KV Vo   | ntithadi                         | S.S.Code | e: 021111      |
| C. | NAME OF THE FEEDER.                           | $\Longrightarrow$ | 11 KV Town  |                                  | Feeder C | Code :02111103 |
| D. | TYPE OF THE FEEDER                            | $\Longrightarrow$ | Town  |                                  |          |                |
| E. | PEAK LOAD IN AMPS.                            | $\Longrightarrow$ | 85  |                                  |          |                |
| F. | AVERAGE POWER FACTOR.                         | $\Longrightarrow$ | 0.92  |                                  |          |                |
| G. | SIZE OF THE CONDUCTOR.                        | $\Longrightarrow$ | 55Sqmm AAAC   |                                  |          |                |
| H. | DETAILS OF ALTERNATIVE SUPPLY.                | $\Longrightarrow$ | 1. RECEIVING FROM<br>2. SENDING TO                              | 11 KV Vontitha<br>Zilla parishad | di Town  |                |
| l. | LENGTH OF 11KV LINE.                          | $\Longrightarrow$ | <ol> <li>Trunk line in KM.</li> <li>Spur Line in KM.</li> </ol> | 2.47 Km<br>2.12 Km               |          |                |
| J. | LENGTH OF LT LINE.                            | $\Longrightarrow$ | <ol> <li>Trunk line in KM.</li> <li>Spur Line in KM.</li> </ol> | 8.8 Km<br>14.25 Km               |          |                |
| K. | % TECHNICAL LOSSES.                           | $\Longrightarrow$ | 1.90%   |                                  |          |                |
|    | % REGULATIONS.                                | $\Longrightarrow$ | 4.39%   |                                  |          |                |
|    | Names of the villages being fed from this for | eeder (Fo         | r Town/MHQ feeder only  | \f ·                             |          |                |
|    |   | ·                 | •   | <i>,</i>                         |          | Town           |
|    | Names of all the Sections being fed from t    | his feeder        | :   |                                  |          | D1             |
|    | No of Distributions being fed from this fee   | der:              |   |                                  |          | 28             |
|    | Wheteher all sections and distributions have  | /e Codes i        | n PAA Data and all cons   | sumers are inde                  | xed:     | Yes            |
|    |   |                   |   |                                  |          |                |


## No. of the DTRs - Capacity wise :

| Capacity    | 315 | 250 | 160 | 100 | 63 | 25 | 15 | Total No. | Total Capacity |
|-------------|-----|-----|-----|-----|----|----|----|-----------|----------------|
| No. of DTRs | 1   | 3   | 2   | 15  | 5  | 1  | 0  | 27        | 3225           |

|        | Category wise consumers &Sales ( Present) |        |        |       |    |   |       |      |       |        |  |  |  |
|--------|---|--------|--------|-------|----|---|-------|------|-------|--------|--|--|--|
|        | Cat.                                      | 1      | 11     | III   | IV | V | VI    | VII  | HT    | Total  |  |  |  |
| Mai.15 | No. of Scs.                               | 3471   | 1110   | 26    | 0  | 0 | 60    | 18   | 2     | 4687   |  |  |  |
|        | Sales                                     | 349378 | 277027 | 21009 | 0  | 0 | 17939 | 3037 | 26584 | 694974 |  |  |  |
|        | Sn Con                                    | 101    | 250    | 808   | 0  | 0 | 299   | 169  | 13292 | 148    |  |  |  |

| 11     | LOSSES THIS YEA | AR :                    |                      |                  |                                |           |                |             |       |                      |
|--------|-----------------|-------------------------|----------------------|------------------|--------------------------------|-----------|----------------|-------------|-------|----------------------|
| SI.No. | Month           | Input to 11KV<br>Feeder | 11KV Direct<br>Sales | Metered<br>Sales | Connected load in AGL services | AGL.Sales | Assessed Units | Total Sales | Loss  | % Loss for the month |
| 1      | 2               | 3                       | 4                    | 5                | 6                              | 7         | 8              | 8           | 9     | 10                   |
| 1      | Jän.15          | 448920                  | 11761                | 413481           | 0                              | 0         | 0              | 425242      | 23678 | 5.27                 |
| 2      | Feb.15          | 519440                  | 14998                | 475923           | 0                              | 0         | 0              | 490921      | 28519 | 5.49                 |
| 3      | Mär.15          | 525280                  | 20568                | 474750           | 0                              | 0         | 0              | 495318      | 29962 | 5.70                 |
| 4      | Apr.15          | 636640                  | 22457                | 577653           | 0                              | 0         | 0              | 600110      | 36530 | 5.74                 |
| 5      | Mai.15          | 732520                  | 26584                | 668390           | 0                              | 0         | 0              | 694974      | 37546 | 5.13                 |

|       | FORMATE- 5       | TOTAL AGR                    | <u>ICULATURAI</u>           | <u> SERVICI</u>                 | ES UNDER                                 | FEEDER :- |  |  |  |  |  |
|-------|------------------|------------------------------|-----------------------------|---------------------------------|--|-----------|--|--|--|--|--|
| s.No. | Catgory          |                              | Details of Agl Consumers    |                                 |  |           |  |  |  |  |  |
|       |                  | No of<br>metered<br>services | Total HP of metred services | No of un<br>metered<br>services | total HP of<br>Un<br>metered<br>services | Assesed   | services<br>availing 24<br>Hours supply. |  |  |  |  |
| 1     | IT assesses.     |                              |                             |                                 |  |           |  |  |  |  |  |
| 2     | Corporate.       |                              |                             |                                 |  |           |  |  |  |  |  |
| 3     | Tatkal.          |                              |                             |                                 |  |           |  |  |  |  |  |
| 4     | Other paying Scs |                              |                             |                                 |  |           |  |  |  |  |  |
| 5     | Free.            |                              |                             |                                 |  |           |  |  |  |  |  |
| 6     | Total.           |                              |                             |                                 |  |           |  |  |  |  |  |



# 4.4.2) 11KV B.Koneru - Town Feeder Regulation Chart

|  | 0.1 | 0.26 | 0.1 | 0.2 | 0.2 | 0.3 | 0.27 | 0.1 | 0.32 | 0.05 | 0.1 | 0.04 | 0.16 | 0.06 | 0.14 | 0.1 | 0.1 | 0.17 | 0.08 |
|--|-----|------|-----|-----|-----|-----|------|-----|------|------|-----|------|------|------|------|-----|-----|------|------|
|  | 250 | 63   | 100 | 100 | 400 | 100 | 63   | 100 | 200  | 63   | 125 | 160  | 163  | 100  | 350  | 250 | 378 | 160  | 100  |

33 / 11kv B.Koneru ss

| D.11011010 00 |      |      |      |      |      |      |      |      |      |      |      |      |      |      |      |     |     |     |     |
|---------------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|------|-----|-----|-----|-----|
| 1x 8 MVA      | 3225 | 2975 | 2912 | 2812 | 2712 | 2312 | 2212 | 2149 | 2049 | 1849 | 1786 | 1661 | 1501 | 1338 | 1238 | 888 | 638 | 260 | 100 |

|       | MOMENT | S    |         |                                   |                |      |
|-------|--------|------|---------|-----------------------------------|----------------|------|
| SI.No | KVA    | KM   | Total   |                                   |                |      |
| 1     | 3225   | 0.10 | 322.50  |                                   |                |      |
| 2     | 2975   | 0.26 | 773.50  | HT<br>Regula <u>0.086</u><br>tion | <u>5751.75</u> | 4.93 |
| 3     | 2912   | 0.10 | 291.20  | 1                                 | 00.00          |      |
| 4     | 2812   | 0.20 | 562.40  |                                   |                |      |
| 5     | 2712   | 0.20 | 542.40  | Hence,<br>Satisfactory            | 4.39%          |      |
| 6     | 2312   | 0.25 | 578.00  |                                   |                |      |
| 7     | 2212   | 0.27 | 597.24  |                                   |                |      |
| 8     | 2149   | 0.20 | 429.80  |                                   |                |      |
| 9     | 2049   | 0.32 | 655.68  |                                   |                |      |
| 10    | 1849   | 0.05 | 92.45   |                                   |                |      |
| 11    | 1786   | 80.0 | 142.88  |                                   |                |      |
| 12    | 1661   | 0.04 | 66.44   |                                   |                |      |
| 13    | 1501   | 0.16 | 240.16  |                                   |                |      |
| 14    | 1338   | 0.06 | 80.28   |                                   |                |      |
| 15    | 1238   | 0.14 | 173.32  |                                   |                |      |
| 16    | 888    | 0.10 | 88.80   |                                   |                |      |
| 17    | 638    | 0.10 | 63.80   |                                   |                |      |
| 18    | 260    | 0.17 | 42.90   |                                   |                |      |
| 19    | 100    | 0.08 | 8.00    |                                   |                |      |
|       |        | TOTA | 5751.75 |                                   |                |      |

## 4.4.3) TECHNICAL LOSSES CALCULATIONS OF 11KV B.KONERU TOWN FEEDER

## Month: MAY 2015

Name of the Feeder: TOWN

Name of the sub station: B.KONERU

Name of the Section: D1, VIZIANAGARAM

1) Units sent out from the 11kv system during a particular month (30 days)= 732520 2) Average Demand = (732520)/(30\*24\*0.965) = 1054.289

3) Peak Demand during the month (1.732\*11\* 85) = 1619.42 KVA

4) Load factor of the month = Average Demand / Peak Demand = 1054.289 /(1.732\*11\*75) = 0.651028766

#### Step:-1

5) Distribution Transformer in the 11KV system - Number and Rating :

| NO         | KVA                  | Total |
|------------|----------------------|-------|
| 1          | 315                  | 315   |
| 3          | 250                  | 750   |
| 2          | 160                  | 320   |
| 15         | 100                  | 1500  |
| 5          | 63                   | 315   |
| 1          | 25                   | 25    |
| Total Tran | nsformers Capacity = | 3225  |

6) Losses when the Demand is equal to total Transformer Capacity .

i) Transformer Iron Losses (ISI Specification)

| No of<br>DTRS | DTR Capacity(in KVA) | Iron Loss(Watts/Each) | Per | Total |
|---------------|----------------------|-----------------------|-----|-------|
| 1             | 315                  | 1200                  | E   | 1200  |
| 3             | 250                  | 1000                  | E   | 3000  |
| 2             | 160                  | 650                   | E   | 1300  |
| 15            | 100                  | 450                   | E   | 6750  |
| 5             | 63                   | 350                   | E   | 1750  |
| 11            | 25                   | 195                   | E   | 195   |
| L             | Total Iro            | on Loss (Watts) =     |     | 14195 |

#### ii) Transformer Copper losses

| No of<br>DTRS | DTR Capacity(in<br>KVA) | Copper losses(Watts/Each) | Per | Total Copper<br>Losses(in Watts) |  |  |  |  |  |
|---------------|-------------------------|---------------------------|-----|----------------------------------|--|--|--|--|--|
| 1             | 315                     | 5700                      | E   | 5700                             |  |  |  |  |  |
| 3             | 250                     | 4500                      | E   | 13500                            |  |  |  |  |  |
| 2             | 160                     | 3000                      | Е   | 6000                             |  |  |  |  |  |
| 15            | 100                     | 2000                      | E   | 30000                            |  |  |  |  |  |
| 5             | 63                      | 1400                      | E   | 7000                             |  |  |  |  |  |
| 1             | 25                      | 700                       | E   | 700                              |  |  |  |  |  |
|               | Total Copper Loss =     |                           |     |                                  |  |  |  |  |  |

#### 11 KV side

315 KVA = 16.54 Amps -----75 KVA =3.94 Amps 250 KVA = 13.13 Amps -----63 KVA = 3.30 Amps 160 KVA = 8.4 Amps -----50 KVA = 2.62 Amps 100 KVA = 5.25 Amps ------15 KVA = 0.79 Amps

11 KV Line Losses (as per Statement -1) =21799.8691 6(iii) Losses for 3 Conductors =

14838.9363 Watts 44516.80897 Watts

#### Step - II

7) Max Demand During the Month =

1619.42 KVA

Total Transformer Capacity=

3225 KVA

Ratio of Max.Demand to the Transformer Capacity = Max. Demand / Total Trans Capacity=

0.502146

i)Transformer Copper Losses ( Correct to M.D )

= Item (6) (ii) \* ( Ratio )2 =

15860.25642

ii)Line Copper losses (Corrected M.D)

= Item (6) (iii) \* (ratio)2 =

| 8) The Losses Calculated above with loss factor                                       |                                  |                                   | _               |
|---|----------------------------------|-----------------------------------|-----------------|
| i) Loss Factor Calculated accord  | h = 0.224867                     |                                   |                 |
| ( As per the statement-<br>ii) Loss factor according to form<br>L.F - Load factor (4) |                                  | 0.2* ( L.F )                      | 0.339           |
| Loss Factor [8(i)]  |                                  | =                                 | 0.224867359     |
| In Case the typical day meter re formulae given above.                                | adings are not available then    | the loss factor has to be calcula | ated by the     |
| i)Corrected transformer copper<br>ii)Corrected line Copper losses                     | 3566.454<br>2524.120             |                                   |                 |
| 9) (i) Units handled during the r<br>Iron Losses [6 (i) ]                             | month (1)                        | =                                 | 732520<br>14195 |
| Copper losses [8 (i) ]  |                                  | =                                 | 3566.454        |
| 11  |                                  | osses [6 (i) + 8 (i) ] =          | 17761.454       |
| (ii) For one Month<br>% Transformer Losses  | =Losses * 720/                   |                                   | 12788.247 KWH   |
| % Hansloffler Losses  | = [ 9 (ii) / 9 (i) ]             | 100 =                             | 1.746           |
| (iii) 11KV Line Losses  |                                  |                                   | 2524.120        |
| 11KV Line losses per mor  |                                  |                                   | 1817.366 KWH    |
|   | = [ Losses per month / 9(i) ] *  | 100 =                             | 0.248           |
| 10) (i) Units handled during the  | month (1)                        | =                                 | 732520          |
| Units billed  |                                  | =                                 | 694974          |
|   | Transformer & L.T = Handle       | d - Billed =                      | 37546           |
| (iv) L.T Distribution losses  |                                  |                                   | 22940.387       |
| % L.T Distribution losses   | =[Losses per month]/9(i)]*       | 100 -                             | 3.132           |
| %Technical +Comm Losses   | = [ Total loss per month]/9(i)*1 | 00                                | 5.12559384      |
| STATEMENT: 1  |                                  |                                   |                 |
| 11KV Line losses;   |                                  |                                   |                 |
| Resistance of line =  | 0.365                            | Ohms/Km for 100Sq,mm              |                 |
|   | 0.5149                           | Ohms/Km for 55Sq.mm               |                 |
|   | 0.9116                           | Ohms/Km for 7/2.59 ACSR           |                 |
|   | 1.37                             | Ohms/Km for 7/2.11 ACSR           |                 |
|   |                                  |                                   |                 |

| Section | Length in KM | Resistance in Ohms | Current (I) | Full load I2R<br>Watts | KVA  |
|---------|--------------|--------------------|-------------|------------------------|------|
|         | 0.29         | 0.1493             | 3.3075      | 1.6335                 | 63   |
|         | 0.3          | 0.1545             | 19.845      | 60.8340                | 378  |
|         | 0.08         | 0.0412             | 5.25        | 1.1354                 | 100  |
|         | 0.165        | 0.0850             | 13.65       | 15.8297                | 260  |
|         | 0.1          | 0.0515             | 33.495      | 57.7674                | 638  |
|         | 0.1          | 0.0515             | 46.62       | 111.9096               | 888  |
|         | 0.33         | 0.1699             | 13.125      | 29.2709                | 250  |
|         | 0.6          | 0.3089             | 18.375      | 104.3107               | 350  |
|         | 0.14         | 0.0721             | 64.995      | 304.5165               | 1238 |
|         | 0.06         | 0.0309             | 70.245      | 152.4421               | 1338 |
|         | 0,2          | 0.1030             | 3.3075      | 1.1266                 | 63   |
|         | 0.365        | 0.1879             | 8.5575      | 13.7629                | 163  |
|         | 0.16         | 0.0824             | 78.8025     | 511.5910               | 1501 |
|         | 0.025        | 0.0129             | 8.4         | 0.9083                 | 160  |
|         | 0.04         | 0.0206             | 87.2025     | 156.6177               | 1661 |
|         | 0.1          | 0.0515             | 1.3125      | 0.0887                 | 25   |
|         | 0.03         | 0.0154             | 5.25        | 0.4258                 | 100  |
|         | 0.08         | 0.0412             | 93.765      | 362.1549               | 1786 |
|         | 0.05         | 0.0257             | 3.3075      | 0.2816                 | 63   |
|         | 0.1          | 0.0515             | 97.0725     | 485.1939               | 1849 |
|         | 0.15         | 0.0772             | 5.25        | 2.1288                 | 100  |
|         | 0.015        | 0.0077             | 5.25        | 0.2129                 | 100  |
|         | 0.06         | 0.0309             | 10.5        | 3.4061                 | 200  |
|         | 0.32         | 0.1648             | 107.5725    | 1906.6694              | 2049 |
|         | 0.1          | 0.0515             | 112.8225    | 655.4119               | 2149 |
|         | 0.1          | 0.0515             | 3.3075      | 0.5633                 | 63   |
|         | 0.27         | 0.1390             | 116.13      | 1874.8888              | 2212 |
|         | 0.25         | 0.1287             | 121.38      | 1896.5189              | 2312 |
|         | 0.06         | 0.0309             | 5.25        | 0.8515                 | 100  |
|         | 0.07         | 0.0360             | 5.25        | 0.9934                 | 100  |
|         | 0.1          | 0.0515             | 10.5        | 5.6768                 | 200  |
|         | 0.02         | 0.0103             | 5.25        | 0.2838                 | 100  |
|         | 0.04         | 0.0206             | 15.75       | 5.1091                 | 300  |
|         | 0.16         | 0.0824             | 5.25        | 2.2707                 | 100  |
|         | 0.1          | 0.0515             | 142.38      | 1043.8086              | 2712 |
|         | 0.06         | 0.0309             | 5.25        | 0.8515                 | 100  |
|         | 0.1          | 0.0515             | 147.63      | 1122.2048              | 2812 |
|         | 0.06         | 0.0309             | 5.25        | 0.8515                 | 100  |
|         | 0.1          | 0.0515             | 152.88      | 1203.4394              | 2912 |
|         | 0.1          | 0.0515             | 156.1875    | 1256.0746              | 2975 |
|         | 0.1          | 0.0515             | 13.125      | 8.8700                 | 250  |
|         | 0.1          | 0.0515             | 169.3125    | 1476.0495              | 3225 |
|         |              |                    |             | 14838.9363             |      |

STATEMENT :-2 Hourly Demand in Amps on the 11 KV feeder on a typical day in the month

| Time in Hours | Current (1) Amps | (Current)2 (1)2 |
|---------------|------------------|-----------------|
| 1.00          | 28               | 784             |
| 2.00          | 26               | 676             |
| 3.00          | 26               | 676             |
| 4.00          | 25               | 625             |
| 5.00          | 28               | 784             |
| 6.00          | 31               | 961             |
| 7.00          | 35               | 1225            |
| 8.00          | 33               | 1089            |
| 9.00          | 31               | 961             |
| 10.00         | 30               | 900             |
| 11.00         | 33               | 1089            |
| 12.00         | 36               | 1296            |
| 13.00         | 36               | 1296            |
| 14.00         | 35               | 1225            |
| 15.00         | 34               | 1156            |
| 16.00         | 34               | 1156            |
| 17.00         | 38               | 1444            |
| 18.00         | 65               | 4225            |
| 19.00         | 85               | 7225            |
| 20.00         | 55               | 3025            |
| 21.00         | 50               | 2500            |
| 22.00         | 43               | 1849            |
| 23.00         | 40               | 1600            |
| 24.00         | 35               | 1225            |
|               |                  | 38992           |

Loss Factor ( L.F ) = Total 2/( Max 2 \* 24 )=

5.1) LOSS CALCULATIONS OF 11KV FEEDERS IN VIZIANAGARAM TOWN

| <u> </u> |                    | COLATIONS OF               |                                |        | Apr-   |               |        |        | May-   | 14.           | ,      |   |
|----------|--------------------|----------------------------|--------------------------------|--------|--------|---------------|--------|--------|--------|---------------|--------|---|
| SL<br>NO | Name of the<br>S/S | 11 kV Feeder<br>Name       | Type<br>of<br>Feede<br>r (T/M) | Input  | Sales  | Loss<br>units | % Loss | Input  | Sales  | Loss<br>units | % Loss | Remarks   |
| 1        | B.Koneru           | P & T - I<br>(Kothapeta)   | Т                              | 394720 | 349179 | 45541         | 11.54  | 330600 | 300568 | 30032         | 9.08   | 0.4Km<br>34sqmm<br>conductor<br>replaced with<br>55sqmm |
| 2        | B.Koneru           | P & T - II<br>(Gajularega) | Т                              | 602240 | 549701 | 52539         | 8.72   | 535920 | 503557 | 32363         | 6.04   | 0.8 Km 34sqmm conductor replaced with 55sqmm            |
| 3        | B.Koneru           | Town Feeder                | Т                              | 736640 | 683092 | 53548         | 7.27   | 657280 | 610007 | 47273         | 7.19   |   |
| 4        | Indoor SS          | TANKBAND                   | Т                              | 237220 | 216229 | 20991         | 8.85   | 212200 | 194383 | 17817         | 8.40   |   |

|          |                    | COLATIONS OF               |                                |        | Jun-   | 14.   |        |   |        | Jul-   | 14.           |        |  |
|----------|--------------------|----------------------------|--------------------------------|--------|--------|-------|--------|---|--------|--------|---------------|--------|--|
| SL<br>NO | Name of the<br>S/S | 11 kV Feeder<br>Name       | Type<br>of<br>Feede<br>r (T/M) | Input  | Sales  | Loss  | % Loss | Remarks   | Input  | Sales  | Loss<br>units | % Loss | Remarks  |
| 1        | B.Koneru           | P & T - I<br>(Kothapeta)   | Т                              | 370880 | 330877 | 40003 | 10.79  | Loss raised due<br>to improper<br>billing and<br>commercial<br>loss | 323600 | 301524 | 22076         | 6.82   | DPE Drive<br>conducted<br>and 0.5Km<br>conductor<br>replaced |
| 2        | B.Koneru           | P & T - II<br>(Gajularega) | Т                              | 586120 | 543315 | 42805 | 7.30   | Loss raised due<br>to improper<br>billing and<br>commercial<br>loss | 532320 | 502239 | 30081         | 5.65   | DPE Drive<br>conducted                                       |
| 3        | B.Koneru           | Town Feeder                | Т                              | 726880 | 672817 | 54063 | 7.44   |   | 646400 | 610518 | 35882         | 5.55   | 0.5Km 34sqmm conductor replaced with 55sqmm                  |
| 4        | Indoor SS          | TANKBAND                   | Т                              | 228600 | 209950 | 18650 | 8.16   |   | 190600 | 178911 | 11689         | 6.13   | 0.4 Km 34sqmm conductor replaced with 55sqmm                 |

|          |                    | OLA HORO GI                |                                |        | Aug-     | 14.           |        |  |        | Sep-   | 14.           |        |   |
|----------|--------------------|----------------------------|--------------------------------|--------|----------|---------------|--------|--|--------|--------|---------------|--------|---|
| SL<br>NO | Name of the<br>S/S | 11 kV Feeder<br>Name       | Type<br>of<br>Feede<br>r (T/M) | Input  | Sales    | Loss<br>units | % Loss | Remarks                                  | Input  | Sales  | Loss<br>units | % Loss | Remarks                                     |
| 1        | B.Koneru           | P & T - I<br>(Kothapeta)   | Т                              | 305513 | 283516.5 | 21996.5       | 7.20   |  | 341720 | 320273 | 21447         | 6.28   | 0.2Km<br>conductor<br>replaced              |
| 2        | B.Koneru           | P & T - II<br>(Gajularega) | Т                              | 564000 | 525661   | 38339         | 6.80   | Loss raised due<br>to commercial<br>loss | 568720 | 539670 | 29050         | 5.11   | DPE Drive<br>conducted                      |
| 3        | B.Koneru           | Town Feeder                | Т                              | 667760 | 625838   | 41922         | 6.28   |  | 650240 | 607303 | 42937         | 6.60   |   |
| 4        | Indoor SS          | TANKBAND                   | Т                              | 206000 | 192181.5 | 13818.5       | 6.71   |  | 198000 | 183117 | 14883         | 7.52   | Loss raised<br>due to<br>commercial<br>loss |

| <u> </u> |                    | OLATIONS OF                |                                |        | Oct-   | 14.           |        |   |        | Nov-   | 14.           |        |         |
|----------|--------------------|----------------------------|--------------------------------|--------|--------|---------------|--------|---|--------|--------|---------------|--------|---------|
| SL<br>NO | Name of the<br>S/S | 11 kV Feeder<br>Name       | Type<br>of<br>Feede<br>r (T/M) | Input  | Sales  | Loss<br>units | % Loss | Remarks   | Input  | Sales  | Loss<br>units | % Loss | Remarks |
| 1        | B.Koneru           | P & T - I<br>(Kothapeta)   | Т                              | 334600 | 315376 | 19224         | 5.75   |   | 298440 | 279851 | 18589         | 6.23   |         |
| 2        | B.Koneru           | P & T - II<br>(Gajularega) | Т                              | 568160 | 529198 | 38962         | 6.86   | Loss raised<br>due to<br>improper<br>billing                | 554160 | 522738 | 31422         | 5.67   |         |
| 3        | B.Koneru           | Town Feeder                | Т                              | 598920 | 565044 | 33876         | 5.66   | 0.4 Km<br>34sqmm<br>conductor<br>replaced<br>with<br>55sqmm | 542120 | 514308 | 27812         | 5.13   |         |
| 4        | Indoor SS          | TANKBAND                   | Т                              | 195800 | 182264 | 13536         | 6.91   | DPE Drive<br>conducted                                      | 181600 | 169999 | 11601         | 6.39   |         |

|          |                    | COLATIONS OF               |                                |        | Dec-   | 14.           |        |             |        | Jan-   | 15.           |        |             |
|----------|--------------------|----------------------------|--------------------------------|--------|--------|---------------|--------|-------------|--------|--------|---------------|--------|-------------|
| SL<br>NO | Name of the<br>S/S | 11 kV Feeder<br>Name       | Type<br>of<br>Feede<br>r (T/M) | Input  | Sales  | Loss<br>units | % Loss | Remark<br>s | Input  | Sales  | Loss<br>units | % Loss | Remark<br>s |
| 1        | B.Koneru           | P & T - I<br>(Kothapeta)   | Т                              | 246280 | 231472 | 14808         | 6.01   |             | 215640 | 203044 | 12596         | 5.84   |             |
| 2        | B.Koneru           | P & T - II<br>(Gajularega) | Т                              | 477360 | 450481 | 26879         | 5.63   |             | 456320 | 429765 | 26555         | 5.82   |             |
| 3        | B.Koneru           | Town Feeder                | Т                              | 546480 | 517355 | 29125         | 5.33   |             | 448920 | 425242 | 23678         | 5.27   |             |
| 4        | Indoor SS          | TANKBAND                   | Т                              | 82800  | 77801  | 4999          | 6.04   |             | 131600 | 124196 | 7404          | 5.63   |             |

# 5.1 ) LOSS CALCULATIONS OF 11KV FE

| SL<br>NO | Name of the<br>S/S | 11 kV Feeder<br>Name       | Type<br>of<br>Feede<br>r (T/M) | Input  | Sales  | Loss<br>units | % Loss | Remarks                                      |
|----------|--------------------|----------------------------|--------------------------------|--------|--------|---------------|--------|--|
| 1        | B.Koneru           | P & T - I<br>(Kothapeta)   | Т                              | 263760 | 245637 | 18123         | 6.87   | Loss raised<br>due to<br>improper<br>billing |
| 2        | B.Koneru           | P & T - II<br>(Gajularega) | Т                              | 524240 | 487925 | 36315         | 6.93   | Loss raised<br>due to<br>improper<br>billing |
| 3        | B.Koneru           | Town Feeder                | Т                              | 519440 | 490921 | 28519         | 5.49   |  |
| 4        | Indoor SS          | TANKBAND                   | Т                              | 127200 | 120128 | 7072          | 5.56   |  |

5.1) LOSS CALCULATIONS OF 11KV FE

FY:- 2014-2015

|          |                    | DOLATIONS OF               |                                |        | Mar-15. |               |        |             | Cummulative Up to MAR-15. |         |               |        |                       |
|----------|--------------------|----------------------------|--------------------------------|--------|---------|---------------|--------|-------------|---------------------------|---------|---------------|--------|-----------------------|
| SL<br>NO | Name of the<br>S/S | 11 kV Feeder<br>Name       | Type<br>of<br>Feede<br>r (T/M) | Input  | Sales   | Loss<br>units | % Loss | Remark<br>s | Input                     | Sales   | Loss<br>units | % Loss | Remark<br>s           |
| 1        | B.Koneru           | P & T - I<br>(Kothapeta)   | Т                              | 295000 | 277861  | 17139         | 5.81   |             | 3720753                   | 3439179 | 281574        | 7.57   |                       |
| 2        | B.Koneru           | P & T - II<br>(Gajularega) | Т                              | 553480 | 522603  | 30877         | 5.58   |             | 6523040                   | 6106853 | 416187        | 6.38   | Losses<br>calculat    |
| 3        | B.Koneru           | Town Feeder                | Т                              | 525280 | 495318  | 29962         | 5.70   |             | 7266360                   | 6817763 | 448597        | 6.17   | ed for<br>one<br>year |
| 4        | Indoor SS          | TANKBAND                   | Т                              | 178400 | 168305  | 10095         | 5.66   |             | 2170020                   | 2017465 | 152556        | 7.03   |                       |

5.1) LOSS CALCULATIONS OF 11KV FE

|          |                    | OLATIONS OF                |                                |        | APR -15. |               |        |         | MAY-15. |        |               |        |         |
|----------|--------------------|----------------------------|--------------------------------|--------|----------|---------------|--------|---------|---------|--------|---------------|--------|---------|
| SL<br>NO | Name of the<br>S/S | 11 kV Feeder<br>Name       | Type<br>of<br>Feede<br>r (T/M) | Input  | Sales    | Loss<br>units | % Loss | Remarks | Input   | Sales  | Loss<br>units | % Loss | Remarks |
| 1        | B.Koneru           | P & T - I<br>(Kothapeta)   | Т                              | 354560 | 334428   | 20132         | 5.68   |         | 363120  | 342636 | 20484         | 5.64   |         |
| 2        | B.Koneru           | P & T - II<br>(Gajularega) | Т                              | 633520 | 595726   | 37794         | 5.97   |         | 624080  | 586401 | 37679         | 6.04   |         |
| 3        | B.Koneru           | Town Feeder                | Т                              | 636640 | 600110   | 36530         | 5.74   |         | 732520  | 694974 | 37546         | 5.13   |         |
| 4        | Indoor SS          | TANKBAND<br>_              | Т                              | 227800 | 216155   | 11645         | 5.11   |         | 193600  | 183855 | 9745          | 5.03   |         |

5.1) LOSS CALCULATIONS OF 11KV FE

FY:-2015-2016

|          |                    | OLA HONE OF                |                                | Cummulative Up to MAY-15. |         |            |        |  |
|----------|--------------------|----------------------------|--------------------------------|---------------------------|---------|------------|--------|--|
| SL<br>NO | Name of the<br>S/S | 11 kV Feeder<br>Name       | Type<br>of<br>Feede<br>r (T/M) | Input                     | Sales   | Loss units | % Loss |  |
| 1        | B.Koneru           | P & T - I<br>(Kothapeta)   | Т                              | 717680                    | 677064  | 40616      | 5.66   |  |
| 2        | B.Koneru           | P & T - II<br>(Gajularega) | T                              | 1257600                   | 1182127 | 75473      | 6.00   |  |
| 3        | B.Koneru           | Town Feeder                | Т                              | 1369160                   | 1295084 | 74076      | 5.41   |  |
| 4        | Indoor SS          | TANKBAND                   | Т                              | 421400                    | 400010  | 21390      | 5.08   |  |

#### 6. FEASIBILITY STUDY

6. Introduction: On the part of this project, 4 Nos 11KV feeders will be studied and the statistics data of the feeders like length of 11KV feeders and Distribution Transformers existing on that feeders and the materials used in the feeders are surveyed physically and then the reports were submitted on the losses of the each feeders in the previous chapters.

In this feasibility study, the line loss of the 11KV Kothapeta Feeder which is emanating from 33/11 KV B.Koneru SS was calculated with based on the conductor size. The energy losses calculated by using the Kelvin's law and also suggestions were made for replacement of conductor with proper size to reduce the energy losses.

#### **Comparative Studies:**

### 6.1) Technical Loss calculation of 11KV Kothapeta feeder with 34 SQmm Conductor

Month: MAY - 2015

Name of the Feeder : KOTHAPETA

Name of the sub station: 33/11KV B.KONERU
Name of the Section: D1, VIZIANAGARAM

1) Units sent out from the 11kv system during a particular month (30 days)

363120

2) Average Demand = (363120)/(30\*24\*0.965) = 522.625

3) Peak Demand during the month (1.732\*11\*45) = 857.34 KVA

4) Load factor of the month = Average Demand / Peak Demand = 522.625 (1.732\*11\*45) = 0.609589213

#### Step:1

#### 5) Distribution Transformer in the 11KV system - Number and Rating:

| No  | KVA             | Total |
|-----|-----------------|-------|
| 0   | 250             | 0     |
| 0   | 200             | 0     |
| 1   | 160             | 160   |
| 11  | 100             | 1100  |
| 0   | 75              | 0     |
| 0   | 63              | 0     |
| 1   | 25              | 25    |
| Tot | al Transformers |       |
|     | Capacity =      | 1285  |

# 6) Losses when the Demand is equal to total Transformer Capacity:

i) Transformer Iron Losses (ISI Specification)

| No of DTRS | DTR Capacity(in<br>KVA) | Iron Loss<br>(Watts/Each) | Per | Total |
|------------|-------------------------|---------------------------|-----|-------|
| 0          | 250                     | 1000                      | Е   | 0     |
| 0          | 200                     | 825                       | Е   | 0     |
| 1          | 160                     | 650                       | Е   | 650   |
| 11         | 100                     | 450                       | Е   | 4950  |
| 0          | 75                      | 385                       | Е   | 0     |
| 0          | 63                      | 350                       | E   | 0     |
| 1          | 25                      | 195                       | Е   | 195   |
|            | Total Iron L            | oss (Watts) =             |     | 5795  |

ii) Transformer Copper losses:

| No of<br>DTRS | DTR Capacity(in KVA) | Copper losses (Watts/Each) | Per | Total Copper<br>Losses(in<br>Watts) |
|---------------|----------------------|----------------------------|-----|-------------------------------------|
| 0             | 250                  | 4500                       | Е   | 0                                   |
| 0             | 200                  | 3750                       | E   | 0                                   |
| 1             | 160                  | 3000                       | Е   | 3000                                |
| 11            | 100                  | 2000                       | Е   | 22000                               |
| 0             | 75                   | 1600                       | E   | 0                                   |
| 0             | 63                   | 1400                       | Е   | 0                                   |
| 1             | 25                   | 700                        | Е   | 700                                 |
|               | Total Copp           | per Loss =                 |     | 25700                               |

#### 11 KV side

11 KV Line Losses (as per Statement -1) 1752.7707 Watts 6(iii) Losses for 3

Conductors = 5258.312211 Watts

#### Step - II

7) Max Demand During the Month = 857.34 KVA
Total Transformer Capacity= 1285 KVA

Ratio of Max.Demand to the Transformer Capacity= Max. Demand / Total

DTR Cap= 0.667190661

i)Transformer Copper Losses (Correct to M.D) = Item (6) (ii) \* (Ratio)2 = 11440.18483

ii)Line Copper losses ( Corrected M.D ) = Item (6 ) ( iii ) \* ( ratio )2 = 2340.702864 Step-III

- 8) The Losses Calculated above have to be corrected to actual loading conditions by multiplying it with loss factor
  - i) Loss Factor Calculated according to the hourly meter Readings of a
    typical day in the month = 0.309510031
    ( As per the statement-2 )

per me statement 2 )

ii) Loss factor according to formulae loss factor = 0.8 (L.F)2 + 0.2\* (L.F) 0.419 L.F - Load factor (4) = 0.309510031

In Case the typical day meter readings are not available then the loss factor has to be calculated by the formulae given above.

| i) Corrected transformer copper losses (actual loading condition) = 7 (i) *  L.F = 3540.852 |   |             |     |  |  |  |
|---|---|-------------|-----|--|--|--|
| ii) Corrected line Copper losses ( actu   | - val leading Conditions )= 7 (ii)* I F | 3340.632    |     |  |  |  |
| 11) Corrected line Copper losses ( actu   | ial loading Conditions )— / (ii) L.i    | 724.471     |     |  |  |  |
| 9) (i) Units handled during the month (1)   | =                                       | 363120      |     |  |  |  |
| Iron Losses [6 (i)]   | =                                       | 5795        |     |  |  |  |
| Copper losses [8 (i) ]  | =                                       | 3540.852    |     |  |  |  |
| copper resses to (1) i  | Losses $[6 (i) + 8 (i)] =$              | 9335.852    |     |  |  |  |
|   | - 1, 11 -                               |             |     |  |  |  |
| (ii) For one Month  | =Losses * 720 / 1000 =                  | 6721.813    | KWH |  |  |  |
| % Transformer Losses  | = [9(ii)/9(i)] * 100 =                  | 1.851       |     |  |  |  |
|   |   |             |     |  |  |  |
| (iii) 11KV Line Losses  |   | 724.471     |     |  |  |  |
| 11KV Line losses per month  | = 8 (ii) * 720/1000 =                   | 521.619     |     |  |  |  |
| % 11 KV Line losses = [ Losses  | s per month / 9(i) ] *100 =             | 0.144       |     |  |  |  |
| 10) (i) Units handled during the month (1)  | ) =                                     | 363120      |     |  |  |  |
| Units billed  | =                                       | 342636      |     |  |  |  |
| Actual losses in 11KV line, Transfe   | ormer & L.T = Handled - Billed =        | 20484.000   |     |  |  |  |
| (ii) L.T Distribution losses  |   | 13240.567   |     |  |  |  |
| % L.T Distribution losses =[Lo  | osses per month ] / 9(i) ] * 100 -      | 3.646       |     |  |  |  |
| %Technical +Comm Losses = [ Total lo  | ss per month]/9(i)*100                  | 5.641110377 |     |  |  |  |

#### **STATEMENT: 1**

11KV Line losses;

| Resistance of line = | 0.365  | Ohms/Km | 100Sq,mm    |
|----------------------|--------|---------|-------------|
|                      | 0.5149 | Ohms/Km | 55Sq.mm     |
|                      | 0.8506 | Ohms/Km | 34Sq.mm     |
|                      | 0.9116 | Ohms/Km | 7/2.59 ACSR |
|                      | 1 37   | Ohms/Km | 7/2 11 ACSR |

| Section | Length in KM | Resistance in Ohms | Current (I) | Full load<br>I2R Watts | KVA |
|---------|--------------|--------------------|-------------|------------------------|-----|
|         | 0.01         | 0.0085             | 5.25        | 0.2344                 | 100 |
|         | 0.01         | 0.0085             | 8.4         | 0.6002                 | 160 |
|         | 0.36         | 0.3062             | 13.65       | 57.0549                | 260 |
|         | 0.05         | 0.0425             | 5.25        | 1.1722                 | 100 |
|         | 0.1          | 0.0851             | 5.25        | 2.3445                 | 100 |
|         | 0.1          | 0.0851             | 5.25        | 2.3445                 | 100 |
|         | 0.1          | 0.0851             | 29.4        | 73.5225                | 560 |
|         | 0.1          | 0.0851             | 34.65       | 102.1249               | 660 |
|         | 0.08         | 0.0680             | 5.25        | 1.8756                 | 100 |
|         | 0.1          | 0.0851             | 5.25        | 2.3445                 | 100 |
|         | 0.2          | 0.1701             | 45.15       | 346.7934               | 860 |
|         | 0.11         | 0.0936             | 1.3125      | 0.1612                 | 25  |

| 0.1   | 0.0851 | 5.25    | 2.3445    | 100  |
|-------|--------|---------|-----------|------|
| 0.25  | 0.2127 | 6.5625  | 9.1581    | 125  |
| 0.09  | 0.0766 | 51.7125 | 204.7194  | 985  |
| 0.25  | 0.2127 | 56.9625 | 689.9911  | 1085 |
| 0.1   | 0.0851 | 5.25    | 2.3445    | 100  |
| 0.065 | 0.0553 | 62.2125 | 213.9903  | 1185 |
| 0.04  | 0.0340 | 5.25    | 0.9378    | 100  |
| 0.01  | 0.0085 | 67.4625 | 38.7124   | 1285 |
|       |        |         | 1752.7707 |      |

STATEMENT :-2
Hourly Demand in Amps on the 11 KV feeder on a typical day in the month

|               | Current (1) | (Current)2 |
|---------------|-------------|------------|
| Time in Hours | Amps        | (1)2       |
| 1.00          | 15          | 225        |
| 2.00          | 13          | 169        |
| 3.00          | 12          | 144        |
| 4.00          | 12          | 144        |
| 5.00          | 15          | 225        |
| 6.00          | 20          | 400        |
| 7.00          | 22          | 484        |
| 8.00          | 20          | 400        |
| 9.00          | 18          | 324        |
| 10.00         | 14          | 196        |
| 11.00         | 15          | 225        |
| 12.00         | 15          | 225        |
| 13.00         | 16          | 256        |
| 14.00         | 16          | 256        |
| 15.00         | 15          | 225        |
| 16.00         | 15          | 225        |
| 17.00         | 18          | 324        |
| 18.00         | 25          | 625        |
| 19.00         | 36          | 1296       |
| 20.00         | 28          | 784        |
| 21.00         | 27          | 729        |
| 22.00         | 27          | 729        |
| 23.00         | 24          | 576        |
| 24.00         | 21          | 441        |
|               |             | 9627       |

Loss Factor (L.F) = Total 2/(Max 2 \* 24) = 0.309510031

### 6.2Technical Loss calculation of 11KV Kothapeta feeder with 55 SQmm Conductor

Month: MAY - 2015

Name of the Feeder : KOTHAPETA

Name of the sub station: 33/11KV B.KONERU Name of the Section: D1, VIZIANAGARAM

1) Units sent out from the 11kv system during a particular month (30day) 363120

2) Average Demand = (363120)/(30\*24\*0.965) = 522.625

3) Peak Demand during the month (1.732\*11\*45) = 857.34 KVA

4) Load factor of the month = Average Demand / Peak Demand = 522.625 /(1.732\*11\*45) = 0.60958921 Step:-1

#### 5) Distribution Transformer in the 11KV system - Number and Rating:

| No         | KVA          | Total |
|------------|--------------|-------|
| 0          | 250          | 0     |
| 0          | 200          | 0     |
| 1          | 160          | 160   |
| 11         | 100          | 1100  |
| 0          | 75           | 0     |
| 0          | 63           | 0     |
| 1          | 25           | 25    |
| Total '    | Transformers |       |
| Capacity = |              | 1285  |

# 6) Losses when the Demand is equal to total Transformer Capacity:

i) Transformer Iron Losses (ISI Specification)

| No of<br>DTRS             | DTR<br>Capacity(in<br>KVA) | Iron Loss<br>(Watts/Each) | Per  | Total |
|---------------------------|----------------------------|---------------------------|------|-------|
| 0                         | 250                        | 1000                      | Е    | 0     |
| 0                         | 200                        | 825                       | E    | 0     |
| 1                         | 160                        | 650                       | Е    | 650   |
| 11                        | 100                        | 450                       | Е    | 4950  |
| 0                         | 75                         | 385                       | Е    | 0     |
| 0                         | 63                         | 350                       | E    | 0     |
| 1                         | 25                         | 195                       | Е    | 195   |
| Total Iron Loss (Watts) = |                            |                           | 5795 |       |

ii) Transformer Copper losses:

| No of DTRS          | DTR<br>Capacity(in<br>KVA) | Copper losses (Watts/Each) | Per | Total<br>Copper<br>Losses(in<br>Watts) |
|---------------------|----------------------------|----------------------------|-----|--|
| 0                   | 250                        | 4500                       | Е   | 0                                      |
| 0                   | 200                        | 3750                       | E   | 0                                      |
| 1                   | 160                        | 3000                       | Е   | 3000                                   |
| 11                  | 100                        | 2000                       | Е   | 22000                                  |
| 0                   | 75                         | 1600                       | Е   | 0                                      |
| 0                   | 63                         | 1400                       | Е   | 0                                      |
| 1                   | 25                         | 700                        | Е   | 700                                    |
| Total Copper Loss = |                            |                            |     | 25700                                  |

#### 11 KV side

11 KV Line Losses (as per Statement -1) 1061.0177 Watts 6(iii) Losses for 3

Conductors = 3183.053089 Watts

#### Step-II

7) Max Demand During the Month = 857.34 KVA
Total Transformer Capacity= 1285 KVA

Ratio of Max. Demand to the Transformer Capacity = Max. Demand / Total

Trans Capacity= 0.66719066

i)Transformer Copper Losses (Correct to M.D)=Item (6) (ii) \* (Ratio )2 = 11440.1848

ii)Line Copper losses ( Corrected M.D ) = Item (6 ) ( iii ) \* ( ratio )2 = 1416.91501 Step-III

8) The Losses Calculated above have to be corrected to actual loading conditions by multiplying it with loss factor

i) Loss Factor Calculated according to the hourly meter Readings of a typical day in the month =

0.30951003

(As per the statement-2)

ii) Loss factor according to formulae loss factor = 0.8 (L.F)2 + 0.2\* (L.F)

0.419

L.F - Load factor (4) Loss Factor [8(i)]

= 0.30951003

In Case the typical day meter readings are not available then the loss factor has to be calculated by the formulae given above.

i) Corrected transformer copper losses (actual loading condition) = 7 (i) \*

L.F = 3540.852

ii) Corrected line Copper losses (actual loading Conditions)= 7 (ii)\* L.F

438.549

| 9) (i) Units handled during the month (1)  Fron Losses [6 (i)]  Copper losses [8 (i)]  | =<br>=   | =          | 363120<br>5795<br>3540.852  |     |
|--|--|------------|---|-----|
| orpor some [1 (4)]   | Losses $[6(i) + 8(i)]$                                 | ==         | 9335.852  |     |
| (ii) For one Month % Transformer Losses  | =Losses * 720 / 1000 =<br>= [ 9 (ii) / 9 (i) ] * 100 = |            | 6721.813<br>1.851   | KWH |
| (iii) 11KV Line Losses 11KV Line losses per month % 11 KV Line losses = [ Losse 10) (i) Units handled during the month (1 Units billed Actual losses in 11KV line, Transf = (ii) L.T Distribution losses | =  | =<br>illed | 438.549<br>315.756<br>0.087<br>363120<br>342636<br>20484.000<br>13446.431 |     |
| % L.T Distribution losses =[L  | osses per month ] / 9(i) ] * 10                        | 00 -       | 3.703   |     |
| %Technical +Comm Losses = [ Total lo   | oss per month]/9(i)*100                                |            | 5.64111038  |     |

# **STATEMENT: 1**

11KV Line losses; Resistance of line

| = | 0.365  | Ohms/Km | 100Sq,mm    |
|---|--------|---------|-------------|
|   | 0.5149 | Ohms/Km | 55Sq.mm     |
|   | 0.9116 | Ohms/Km | 7/2.59 ACSR |
|   | 1 37   | Ohms/Km | 7/2.11 ACSR |

| Section | Length in KM | Resistance in Ohms | Current (I) | Full load<br>I2R Watts | KVA  |
|---------|--------------|--------------------|-------------|------------------------|------|
|         | 0.01         | 0.0051             | 5.25        | 0.1419                 | 100  |
|         | 0.01         | 0.0051             | 8.4         | 0.3633                 | 160  |
|         | 0.36         | 0.1854             | 13.65       | 34.5375                | 260  |
|         | 0.05         | 0.0257             | 5.25        | 0.7096                 | 100  |
|         | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100  |
|         | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100  |
|         | 0.1          | 0.0515             | 29.4        | 44.5059                | 560  |
|         | 0.1          | 0.0515             | 34.65       | 61.8201                | 660  |
|         | 0.08         | 0.0412             | 5.25        | 1.1354                 | 100  |
|         | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100  |
|         | 0.2          | 0.1030             | 45.15       | 209.9270               | 860  |
|         | 0.11         | 0.0566             | 1.3125      | 0.0976                 | 25   |
|         | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100  |
|         | 0.25         | 0.1287             | 6.5625      | 5.5437                 | 125  |
|         | 0.09         | 0.0463             | 51.7125     | 123.9243               | 985  |
|         | 0.25         | 0.1287             | 56.9625     | 417.6774               | 1085 |
|         | 0.1          | 0.0515             | 5.25        | 1.4192                 | 100  |
|         | 0.065        | 0.0335             | 62.2125     | 129.5363               | 1185 |
|         | 0.04         | 0.0206             | 5.25        | 0.5677                 | 100  |
|         | 0.01         | 0.0051             | 67.4625     | 23.4341                | 1285 |
|         |              |                    |             | 1061.0177              |      |

76

STATEMENT :-2
Hourly Demand in Amps on the 11 KV feeder on a typical day in the month

|               | Current (1) | (Current)2 |
|---------------|-------------|------------|
| Time in Hours | Amps        | (1)2       |
| 1.00          | 15          | 225        |
| 2.00          | 13          | 169        |
| 3.00          | 12          | 144        |
| 4.00          | 12          | 144        |
| 5.00          | 15          | 225        |
| 6.00          | 20          | 400        |
| 7.00          | 22          | 484        |
| 8.00          | 20          | 400        |
| 9.00          | 18          | 324        |
| 10.00         | 14          | 196        |
| 11.00         | 15          | 225        |
| 12.00         | 15          | 225        |
| 13.00         | 16          | 256        |
| 14.00         | 16          | 256        |
| 15.00         | 15          | 225        |
| 16.00         | 15          | 225        |
| 17.00         | 18          | 324        |
| 18.00         | 25          | 625        |
| 19.00         | 36          | 1296       |
| 20.00         | 28          | 784        |
| 21.00         | 27          | 729        |
| 22.00         | 27          | 729        |
| 23.00         | 24          | 576        |
| 24.00         | 21          | 441        |
|               |             | 9627       |

#### **RESULTS**

### 6.3) Saving of Energy due to Providing of second LT Circuit :-

If One Circuit Carries 80 Amps current

Then Copper losses in the Circuit will be(I\*I\*R) = 80\*80\*0.5149 = 9695 Watts

Then energy Loss Per month will be = (9.6\*720)/1000 = 6.912 KWH

If the second circit was run and some load was diverted on that feeder

let load on the first circuit = 50A

let load on the second circuit = 30A

Then Copper losses on the first Circuit will be(I\*I\*R) = 50\*50\*0.5149 = 1287 Watts

Then Copper losses on the second Circuit will be(I\*I\*R) = 30\*30\*0.5149 = 463 Watts

Total Losses due to Both the circuits will be = 1287 Watts + 463 Watts = 1750 Watts

Then energy Loss Per month will be =(1.75 \*720)/1000 = 1.26 KWH

Then Saving of energy per month after run the second circuit will be = 6.912 - 1.26 = 5.652 KWH

#### 6.4) Saving of Energy due to conductor replacement

In Kothapeta feeder when ever the conductor was 34 Sqmm Size the losses due to conductor was 5258 Watts then per month it will become = (5258) \*720/1000 Units = 3785 units

In Kothapeta feeder when ever the conductor was 55 Sqmm Size the losses due to conductor was 3183 Watts then per month it will become = (3183) \*720/1000 Units = 2291 units

Then Saving of Units per month due to conductor replacement was = (3785 - 2291) = 1494 Units Amount Saved per month due to replacement of conductor was = 1494\* Rs 3.82 = Rs 5707/-

#### Total Expenditure on Replacement of coductor

| Length of the line  |    | 2 Km   |
|---|----|--------|
| 55 Sq mm Conductor required                                     |    | 6 Km   |
| Cost of the 6 Km Conductor (Rs19086/- per Km)                   | Rs | 114516 |
| Labour Charges for relacing the 6KM Conductor (Rs 1785/-per KM) |    | 10710  |
| Total Expenditure on Replacement of coductor                    |    | 125226 |

#### Revenue Return due to conductor replacemet

Amount Saved per month due to replacement of conductor was = Rs 5707/-

In No of Months the amount of expenditure for conductor replacement was returned = Rs 125226/ Rs 5707 = 22 Months

#### 7. CONCLUSION:-

- 1) From the above it is observed that by providing of 2nd LT Circuit the saving of energy is 5.652 KWH per month.
- 2) It is also observed that by replacing the 34 sqmm conductor on 11KV Kothapeta feeder with
- 55 Sqmm conductor the saving of energy is 1494 units per month.
- 3) Amount Saved per month due to replacement of conductor was Rs 5707/-.
- 4) And also observed that amount of expenditure for conductor replacement was returned in 22 months.

# **BIBLIOGRAPHY**

- 1) Electrical power systems by C.L. Wadhwa
- 2) Electrical Energy systems by Mohamed E.El-Hawary
- 3) Power Distribution planning reference book by H. Lee Willis
- 4) APSEB Volume –I & II (Technical Reference book)